



Bangalore Electricity Supply Company Limited
(wholly owned Government of Karnataka undertaking)

Telephone : 080-2234 0816

Email ID : gmdsm@bescom.co.in, gmdsm.work@gmail.com

Ref No. : BESCOM/BC-51/GM(DSM)/2025-26/CYS-48

Encl : Common SOP for DSPV Projects

Office of the
General Manager (Ele).,
DSM, Corporate Office,
BESCOM, K.R. Circle,
Bangalore-560 001.
Date:01.12.2025

CIRCULAR

Sub: Common Standard Operating Procedure for BESCOM, HESCOM, GESCOM, CESC, MESCOM & HRECS for implementation of Distributed Solar PV Projects(DSPV) in the state of Karnataka.

Ref:

1. G.O No: ENERGY/346/VSC/2023 Bengaluru dated 11.01.2024 Government.
2. G.O No: ENERGY 346 VSC 2023 BENGALURU, Dated 24.05.2024
3. Common SOP for Implementation of SRTPV Scheme Dated:04.07.2024

PREAMBLE:

The Energy Department, Government of Karnataka, vide Government Order No. ENERGY 346 VSC 2023, Bengaluru, dated 24.05.2024, issued directives for the implementation of Solar Rooftop Projects across the State. In accordance with the said Government Order, BESCOM was mandated to develop the procedure and a Common Standard Operating Procedure (SOP) for SRTPV implementation and circulate the same to all ESCOMs for uniform adoption.

In pursuance of these directions, BESCOM prepared the Common SOP, which was issued vide Circular No. BESCOM/BC-51/2024-25/CYS-23, dated 04.07.2024 and the same was subsequently adopted by all ESCOMs. Consequent to the issuance of the KERC Generic Tariff Order dated 09.07.2025, the existing Common SOP has been revised, updated, and aligned with the provisions of the said Tariff Order.

Hence this Circular;

In pursuance of the directions issued by the Government of Karnataka (GoK), all ESCOMs of the State—BESCOM, HESCOM, MESCOM, GESCOM, CESC, and HRECS—have to adopt and implement the Common Standard Operating Procedure (SOP) for the execution of Distributed Solar PV (DSPV) Projects in Karnataka, as enclosed with this circular.

The Common SOP is required to be host on their respective official websites of ESCOMs, ensuring its accessibility to consumers, developers, stakeholders and field officials.

For ready reference, the main highlights are also enclosed with this circular.

Approved by MD, BESCOM

General Manager (DSM)
BESCOM, Bangalore

Copy submitted for kind information to:

1. The Chief Engineer (Operations), Corporate Office, GESCOM, Kalburgi with a request to issue necessary directions for implementation as per this circular.

Copy submitted to:


1. The Chairman, Hukkeri Rural Electricity Co-operative Society(HRECS) with a request to implement the circular.
2. The General Manager (Projects), Corporate Office, CESC, Mysore with a request to implement the circular.
3. The General Manager (Tech), Corporate Office, HESCOM, Hubballi with a request to implement the circular.
4. The Superintending Engineer (Comml), Corporate Office, MESCOM, Mangalore with a request to implement the circular.

Copy for kind information to

5. PS to MD/D(T), BESCOM with a request to place it before the Chair.
6. PS to MD/D(T), HESCOM with a request to place it before the Chair.
7. PS to MD/D(T), MESCOM with a request to place it before the Chair.
8. PS to MD/D(T), GESCOM with a request to place it before the Chair.
9. PS to MD/D(T), CESC with a request to place it before the Chair.

Main Highlights of the Common SOP are as below:

1. The SRTPV nomenclature has been changed to DSPV Plants (Distributed Solar PV plants).
2. The permissible locations for Installation of Solar PV panels are: on the walls of buildings as *façade-integrated solar installations*, on the rooftop of buildings, on elevated structures within the premises with minimum clearance of 8 (eight) feet subject to compliance with applicable building bye-laws and adherence to all relevant safety regulations/standards.
3. The minimum permissible capacity of a DSPV plant shall be 1 kW (DC). The maximum capacity shall be limited up to the sanctioned load of the consumer's installation.
4. The consumers are allowed to install the Distributed Solar PV grid tied plants with Generators and hybrid grid tied inverter with the battery.
5. No PPA is required for LT domestic Consumers i.e. upto DSPV capacity of 150kW. The online application format covers all the terms and conditions for implementation of Distributed Solar PV Plants with net /gross metering.
6. The online PPA shall be executed by the Consumer for all the DSPV applications which are considered as deemed feasible i.e. for all applications upto 150kW capacity of other than LT domestic Consumers.
7. The offline PPAs shall be executed for DSPV applications of more than 150kW capacity. The PPAs are to be executed on Rs. 500 value non-judicial stamp paper in Commission approved format.
8. For capacities upto 500kWp, Assistant Executive Engineer(Ele) of the O & M Sub-Division is the PPA approval authority.
9. For capacities above 500kWp and upto & inclusive of 1000kWp, PPAs shall be approved by Corporate Office of the respective ESCOMs.
10. The approval of the KERC shall be obtained for all PPAs of DSPV applications with capacities of above 1000kW.
11. If a Consumer requests for installation of additional solar capacity, the present PPA shall be canceled and new PPA shall be executed for 25 years with PPA rate being 90% of PPA tariff or present tariff, whichever is lower.
12. No hard copies of the documents, except for PPA in case of offline PPA, shall be collected from Consumer / Installer. If required, documents shall be downloaded by AE(T)/AAO using their login credentials.
13. For subsidy applications, after synchronization in ESCOM portal, the AEE of C,O&M sub-division should mandatorily complete Inspection Approval in the MNRE portal as per the MNRE guidelines.
14. The check meter shall be provided for DSPV systems of capacity more than 50kWp.
15. In case, if the change of HT Metering Cubicle is required, the sub division officers shall prepare estimate and intimate to the Consumer the supervision charges to be paid, within 07 days of PPA execution.
16. Installation of smart meter is mandatory for DSPV installations upto capacity 50kW. Both the bidirectional meter and solar generation meter should be smart meter.


General Manager (DSM)
BESCOM, Bangalore

The first part of the paper discusses the general theory of the model. It is shown that the model is well-posed and that the solution is unique. The second part of the paper discusses the numerical solution of the model. It is shown that the numerical solution is stable and that the error is of order $O(\Delta t^2)$.

The third part of the paper discusses the application of the model to the problem of the stability of a structure. It is shown that the model is able to predict the stability of a structure under various loading conditions. The fourth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

The fifth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The sixth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

The seventh part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The eighth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

The ninth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The tenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

The eleventh part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The twelfth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

The thirteenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The fourteenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

The fifteenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The sixteenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.


The seventeenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions. It is shown that the model is able to predict the stability of a structure under various loading conditions. The eighteenth part of the paper discusses the application of the model to the problem of the stability of a structure under various loading conditions.

11/11/11



Common Standard Operating Procedure for implementation of Distributed Solar Photovoltaic (DSPV) Plants in the State of Karnataka

Prepared by DSM Section BESCOM



COMMON STANDARD OPERATING PROCEDURE FOR IMPLEMENTATION OF DISTRIBUTED SOLAR PV (DSPV) PROJECTS

(SRTPV shall hereafter be referred to as DSPV)

Index

Sl. No.	Particulars	Page No.
I	Preamble & Orders Reference	1-2
II	The Gist Of Frequently Referred Terminologies	3-12
III	Procedure for Installation of Solar Rooftop Plants	13-24
IV	Accounting & Billing	24
V	Timelines	25-26
VI	Schematic Diagrams	27-28
VII	Illustration of Procedure	29-78

I. PREAMBLE:

The Energy Department, Government of Karnataka, through Government Order No. ENERGY 346 VSC 2023, Bengaluru, dated 24.05.2024, issued directives for the implementation of Solar Rooftop Projects in the State.

In pursuance of these directives, it was mandated that BESCOM to develop the procedure and Standard Operating Procedure (SOP) for SRTPV implementation and circulate to all other ESCOMs, who in turn should follow without any deviation.

Accordingly, BESCOM prepared the Common SOP, which was issued vide Circular No. BESCOM/BC-51/2024-25/CYS-23 dated 04.07.2024, and subsequently adopted by all ESCOMs.

With the issuance of the KERC Generic Tariff Order dated 09.07.2025, the existing Common SOP now requires modification and updation.

The revised procedure and SOP detailed below shall be read with the following Regulations and Orders and its modifications issued thereof:

Table No.1

Sl. No	Issued By	Date	Description
1	KERC	19.09.2016.	Modifications to the order dated 2 nd May 2016 in respect of Determination of tariff and other norms for Solar Rooftop and small Photovoltaic power plants
2	KERC	15.12.2016	The KERC (Implementation of Solar Rooftop Photovoltaic Power Plants), Regulations 2016
3	KERC	15.09.2017	Tariff and other Operational Procedures applicable for Multiple/Combined SRTPV in single premise
4	Energy Department	19.07.2018	Notification No: EN 106 EBS 2018, Bengaluru dated 19.07.2018 regarding tax on self-consumption.
5	Energy Department	27.08.2018	Inspection by Electrical Inspector for the Generating Units including Solar Rooftop Units

Sl. No	Issued By	Date	Description
6	KERC	09.12.2019	Decision on Various Models and Guidelines for SRTPV allowed to be installed on consumer's rooftop
7	MNRE, GoI.	10.06.2022	Guidelines for simplified procedure
8	KERC	18.07.2022	Net metering arrangement for eligible consumers of Solar Rooftop Photovoltaic (SRTPV) plant.
9	KERC	02.03.2023	Evacuation / Utilization of Solar Energy Generation at LT/HT Voltage and connect to their LT/HT system
10	MNRE, GoI.	17.05.2023	OM for empanelment of Vendors
11	KERC	01.06.2023	Determination of tariff for SRTPV plants for FY-2023-24
12	Energy Department	11.01.2024	GO No: ENERGY/ 346/VSC/2023 Bengaluru Formation of Expert Committee.
13	KERC	06.03.2024.	KERC (Pre-paid Smart Metering) Regulations, 2024
14	Energy Department	04.05.2024	Report of the Expert Committee
15	MNRE, GoI	07.06.2024	Operational Guidelines for Implementation of PM Surya Ghar: Muft Bijli Yojana for the component "CFA to the Residential Consumers"
16	KERC	11.06.2024	Determination of tariff for SRTPV plants for FY-2025
17	KERC	26.11.2024	KERC (Fee) Regulation 2024
18	KERC	05.12.2024	Enhancement of sanctioned load up to and inclusive of 10 kW for SRTPV Consumers and other related matters
19	MNRE, GoI	07.06.2025	Amendment in Guidelines for Implementation of PM Surya Ghar: Muft Bijli Yojane
20	KERC	09.07.2025	Determination of tariff for SRTPV plants for FY-2025
21	KERC	17.06.2006	Conditions of Supply of Electricity of Distribution Licensees in the State of Karnataka and subsequent amendments issues to it.

Summary of Commonly Used Terminologies in the Implementation of DSPV Projects

1. Installation of Distributed Solar PV (DSPV) Systems

a) Permissible Locations

Installation of Solar PV panels shall be permitted on the following areas, subject to compliance with applicable building bye-laws and adherence to all relevant safety regulations/standards:

- On the **walls of buildings** as *façade-integrated solar installations*.
- On the **rooftop of buildings**.
- On **elevated structures within the premises**, constructed from the ground level, provided that such structures maintain a minimum ground clearance of **8 (eight) feet at the lowest point**.

b) Plant Capacity Determination

For the purpose of capacity determination, the **DC capacity** of a DSPV plant shall be reckoned as the *arithmetic sum (total wattage) of the Maximum Power Rating of all installed solar modules/panels*.

c) Minimum and Maximum Capacity

The minimum permissible capacity of a DSPV plant shall be 1 kW (DC). The maximum capacity shall be limited upto the sanctioned load of the consumer's installation.

d) Tolerance in DC Capacity of PV Panels

For installation of SRTPV system up to and inclusive of 10 kW sanctioned load, a capacity tolerance of up to 10% shall be allowed for the applied system capacity (DC), subject to condition that the AC capacity of the inverter shall not exceed the sanctioned load.

e) Conversion of Sanctioned Load

- Where the sanctioned load is expressed in **KVA**, it shall be converted to **kW** by applying a multiplication factor of **0.85 for LT installations & 0.90 for HT installations**.
- Where the sanctioned load is expressed in **HP**, it shall be converted to **kW** by applying a multiplication factor of **0.746**.

f) Provision for Installation of DSPV Plants with Generators and Hybrid Inverters:

The consumers are allowed to install the Distributed Solar PV grid tied plants with Generators especially during periods of low sunlight or grid outages. Even the consumers are allowed to use the hybrid grid tied inverter with the battery to the Distributed Solar PV plant.

g) SOP on Sanctioned Load and Installation of DSPV Plants:**Table No.2**

Provision	Responsibility of	
	Distribution Licensee	Consumer
Installation beyond sanctioned load (up to 10 kW DSPV)	Allow consumer to install SRTPV plant of capacity upto and inclusive of 10kW even if the sanctioned load is less than the solar proposed capacity and the sanctioned load of the consumer shall be enhanced automatically to match the required capacity of SRTPV plant	Shall Apply for the DSPV installation as per the prescribed format.
Augmentation of Network	Where required, augment distribution lines / transformers of the Distribution Licensee to accommodate the enhanced load.	Allow access to premises for augmentation works.
Increased Sanctioned Load	Record enhanced sanctioned load in consumer account. Issue revised demand note for applicable charges and security deposit.	<ul style="list-style-type: none"> • Pay applicable charges • Deposit additional security • Execute Power Supply Agreement(PSA) for additional load.
Compliance Before Commissioning	Verify that consumer obligations have been met before granting commissioning approval for DSPV plant.	<ul style="list-style-type: none"> • Ensure all payments and agreements are completed prior to commissioning.

2. Application & Facilitation Fees:

The applications are broadly considered into following 02 categories;

I. Without Subsidy (Non-Subsidy)

II. With Subsidy (PM Surya Ghar Yojana)

- The registration and the facilitation fee **have been waived off** for the consumers applying under subsidy scheme of DSPV under PM Surya Ghar Yojane.
- The application and facilitation to be paid by Consumer for applying under **non-subsidy DSPV** scheme is as tabulated below;

Table No 3

Sl. No	Capacity of the proposed DSPV system	Registration Fee	Facilitation Fee	Total Amount
1	From 1kWp Upto and inclusive of 5kWp	Rs.500/-	Rs.1000/-	Rs.1,500/- plus applicable GST
2	Above 5kWp Upto and inclusive of 50kWp	Rs.1000/-	Rs.2000/-	Rs.3,000/- plus applicable GST
3	Above 50kWp and Upto 1000kWp	Rs.2000/-	Rs.5000/-	Rs.7,000/- plus applicable GST
4	Above 1000kWp and Upto sanctioned load	Rs.5000/-	Rs.10000/-	Rs.15,000/- plus applicable GST

3. Metering arrangement:

Table No.4

Sl. No	Type of Metering	Eligible Consumers	Remarks
1	Gross Metering / Net Metering	All category of consumers.	As per Commission's Order dated 19.09.2016 , consumers are allowed a one-time irrevocable option of either Gross or Net Metering at the time of signing of PPA/ at the time of providing consent, as the case may be. Consumers under Net Metering opting to procure power through Open Access shall be permitted, subject to the condition that ESCOMs shall not pay for net exported energy . In such cases, a Supplementary PPA (SPPA) shall be executed/consent shall be provided as the case may be.
2	Virtual Net Metering (VNM) & Group Net Metering(GNM)		Separate SoP will be issued

4. Feasibility for LT installations:

Every DSPV plant of less than 150 kW capacity shall be connected only to the existing distribution transformer through which the eligible consumers are being supplied electricity. In such cases, the total capacity of the existing and proposed DSPV plants on that distribution transformer shall not exceed 80% of the rated capacity.

Note:

- i. This is applicable only for LT installations.
- ii. The installations with solar proposed capacity upto 150kW are considered to be deemed feasible. There is no requirement of issuing feasibility reports for such DSPV plants.

5. Feasibility for HT installations:

Every DSPV plant of more than 150 kW capacity shall be connected only to the existing 11 kV distribution system. In such cases, the total capacity of the existing and proposed DSPV plants shall be limited so that line current does not exceed 80 % of the rated current capacity of the line

Note: This is applicable only for HT installations.

6. Installation of More than 150kW plant capacity for LT Consumer:

If a LT consumer requests for installation of DSPV plant of capacity more than 150 kW, the consumer shall convert to HT system i.e., the billing meter shall be HT meter with metering cubicle and solar generation meter shall be 3 phase LT CT Operated meter (For net meter arrangement only).

7. Installation of More than 150kW plant capacity for HT Consumer:

If a HT consumer requests for installation of DSPV plant of capacity more than 150 kW, the billing meter shall be bi-directional HT meter and solar generation meter will be 3 phase LT CT Operated meter (For net meter arrangement only).

8. Power Purchase Agreement:

No requirement of PPA to be executed between the Consumer and the ESCOMs for the Distributed Solar PV Plant capacity with net/gross metering arrangement for LT Domestic Consumers upto 150 kW. The online application format covers all the terms and conditions for implementation of Distributed Solar PV Plants with net /gross metering.

Other than the above, the term of Power Purchase Agreement is for a period of 25 years and the Power Purchase Agreement (PPA) Execution Authority on behalf of ESCOMs are as tabulated below;

Table No.5

Sl. No.	DSPV plant Capacity	PPA Execution Authority
1	From 1kWp to 500kWp	Assistant Executive Engineer(Ele), O & M Sub-Division
2	Above 500kWp	Executive Engineer(Ele) O & M Division

In case of lease agreement, the PPA shall be executed for the duration of lease period or maximum for 25 years, whichever is earlier.

9. Synchronization Authority:

The DSPV plant Commissioning & Synchronizing Authority:

Table No.6

Sl. No.	DSPV Plant Capacities	ESCOM Officers authorized for synchronization
1	1kW upto 35kW with smart meter	Assistant Executive Engineer(Ele), O & M Sub-Division and MT staff not required.
2	Above 35kW upto 50kWp with smart meter	Assistant Executive Engineer(Ele), O & M Sub-Division in co-ordination with Meter Testing (MT) staff.
3	Above 50kW upto 500kWp static meter	Assistant Executive Engineer(Ele) O & M Sub-Division in Co-ordination with Meter Testing (MT) staff
4	Above 500kWp static meter	Executive Engineer(Ele) O & M Division in Co-ordination with Meter Testing (MT) staff

*For all clarifications with regards to the meter, the circulars/orders issued by GM(M&C) from time to time, shall be followed.

10. Installation of Multiple DSPV Plants:

As per KERC order dated:15.09.2017 and tariff order dated:01.06.2023 for FY-2023-24, the following metering arrangements are allowed;

Table No.7

Clause No. as per the Order dated:15.09.2017	Registered Consumer	Details of the SRTPV Units		Metering Arrangement (Net/Gross)
i	Single or multiple Registered Consumer	No Existing SRTPV Unit	Wants to install multiple SRTPV Units	Net
ii	Registered consumer with multiple installations	No Existing SRTPV Unit	Wants to install Single SRTPV Unit	Gross
iii	Multiple Registered Consumer with multiple installations	No Existing SRTPV Unit	Wants to install Single SRTPV Unit	Gross
iv	Multiple Registered Consumer with multiple installations	Having Existing SRTPV Unit of a single consumer	Wants to install multiple SRTPV Units	Net
v	Multiple Registered Consumer with multiple installations	Having Existing SRTPV Unit of a single consumer	Wants to install additional SRTPV unit	Gross

The Commission has allowed the single or multiple registered Consumers to opt for installing DSPV plant /plants with respect to each RR No. separately, under net metering or gross metering as per Commission's order dated 19.09.2016.

11. Option for installation of multiple generation Meters for HT Consumers:

The KERC vide order dated 02.03.2023 has issued order for Evacuation / Utilization of Solar Energy Generation at LT/HT Voltage and connect to their LT/HT system.

The DSPV plant under net-metering arrangement can be installed on the rooftops of the several buildings with different capacities within the same premises, having HT connection with ESCOMs and to evacuate the solar generated energy connecting to the LT voltage bus of each building.

12. Third Party Investment Models:

The Commission has allowed consumers to opt for either net metering or gross metering arrangements, irrespective of the nature of investment in the Distributed Solar PV project.

13. PPAs for additional capacity installation:

In the event a consumer seeks to install additional solar capacity beyond the capacity already commissioned under the existing PPA, the existing PPA shall stand terminated. A fresh PPA shall thereafter be executed for a period of twenty-five (25) years, at a tariff determined as **ninety percent (90%) of the PPA tariff** or the **prevailing generic tariff determined by the Commission at the time of execution**, whichever is lower.

In the event that a consumer seeks enhancement of the sanctioned load, such enhancement shall be permitted, provided that the enhanced sanctioned load does not exceed the solar capacity already commissioned under the existing PPA. In such cases, there shall be no change in the applicable tariff, subject to the following conditions:

- a) The annual energy generation from the plant shall not exceed a Capacity Utilization Factor (CUF) of 19%.
- b) In the event of generation in excess of the 19% CUF, such excess energy shall be injected into the grid free of cost, without any liability on the ESCOM to make payment for the same.
- c) If consumer opts the above, a Supplementary Power Purchase Agreement (SPPA) shall be executed to record and give effect to the above provisions and SPPA shall be approved by the Hon'ble KERC.

Note: In case where the DSPV plant installed is equal to or less than the sanctioned load/contract demand, the tariff rate applicable for change in sanctioned load/tariff category will be **ninety percent (90%) of the PPA tariff** or the **prevailing generic tariff determined by the Commission at the time of execution**, whichever is lower

14. Continuation of PPA for change in location of Distributed Solar PV Plants with net-metering/gross metering as per PPA

If the Consumer who has invested in Solar PV Plants with net-metering/gross metering in a place, decides to shift his Solar PV Installation to a new location, such consumer are allowed to shift the solar PV installation to a new place in the jurisdiction of the same ESCOM and continue the same PPA for remaining PPA term, subject to limiting the solar plant capacity to the original sanctioned load, at new location.

Note: In case of change of sub-division, the SRTPV file along with billing & payment details shall be transferred to the concerned subdivision where the DSPV plant is intended to shift and SPPA shall be executed between consumers & concerned ESCOM officer.

15. Transfer of DSPV installation:

For transfer of DSPV installation in cases where the property is transferred due to sale/gift deed/legal heir due to death of the registered consumer, the same shall be allowed by duly executing SPPA with the new registered consumer at the existing PPA tariff rate for the remaining term.

16. Energy Accounting during faulty Meter/ meters not recording:

The ESCOMs shall calculate the energy generated on the basis of DSPV installed capacity for extending the solar energy generation benefits by considering 19% CUF or if available, analyse historical energy generation/consumption data/excess energy exported to the grid, trends and patterns in energy generation to estimate current energy generation levels.

Provided such meter shall be replaced within the prescribed time period as mandated under Conditions of Supply of Electricity of ESCOMs (CoS) as amended from time to time.

17. Procurement of Smart Meters:

Provision has been made for supply of smart meters in ESCOM outlets. The Consumer has to purchase smart meters from any of the outlets. For installations more than 50KW, the procurement of static meters shall be followed the circulars issued by GM(M&C) from time to time.

18. Provision of Check Meter:

The check meter shall be provided for DSPV systems of capacity more than 50kWp.

19. Procurement of CTs, PTs & Metering Cubicle:

CT's, PT's and Metering Cubicle shall be procured from ESCOM approved Vendors only.

20. Applicable Tariff:

The PPAs shall be executed as per the Generic Tariff Orders issued by KERC from time to time for every FY / Control Period.

21. Gist of other Orders :


- i. To install Distributed Solar PV projects with capacity equivalent to 100% of the sanctioned load of the respective consumer's installation for the purpose of gross or net-metering with their own investments/third party investment.
- ii. To allow installation of Distributed Solar PV projects on Government buildings, as per the Commission's Order dated 11.11.2016, with the tariff for any surplus energy injected as determined by the Commission.
- iii. To allow installation of Distributed Solar PV systems up to and inclusive of 10 kW sanctioned load, a capacity tolerance of up to 10% for the applied system capacity (DC), subject to condition that the AC capacity of the inverter shall not exceed the sanctioned load.
- iv. The consumers are allowed to install Solar panels and other equipment conforming to standards specified by IEEE / BIS, without insisting on procurement from the ESCOMs' empanelled vendors.
- v. Connectivity of Distributed Solar PV installations above 5KW and up to 150 KW at LT level, 3 phase, 400 volts and above 150 KW and up to 2000 KW at 11KV HT. For above 2000kW capacity, the Distributed Solar PV installations shall be connected to the system as specified in the KERC Regulations/ Conditions of Supply of Electricity of Distribution Licensees (COS).
- vi. The PPAs/SPPAs of Distributed Solar PV plants, with an installed capacity up to and inclusive of 1000 kW, executed as per the approved standard PPA/SPPA format, shall be considered as deemed to have been approved by the Commission and the ESCOMs are not required to obtain a separate approval thereon.
- vii. The Commission allows to connect the Distributed Solar PV grid tied plants with Generators especially during periods of low sunlight or grid outages. The Commission allows the consumer to use the hybrid grid tied inverter with the battery to the Distributed Solar PV plant.
- viii. The Commission has detailed the procedure for energy accounting when the meter is faulty or meters are not recording.
- ix. The Commission has removed the capacity restriction of 2000 kW for installing Distributed Solar PV projects and allowed to install the plants up to their sanctioned load/Contract demand.

PROCEDURE FOR INSTALLATION OF SOLAR ROOFTOP PLANTS

The general work flow to be followed for DSPV application consists of following stages:

1. Application Registration
2. Providing Feasibility (If applicable)
3. Execution of Power Purchase Agreement (if applicable)
4. Work Approval Intimation
5. Work Completion Intimation
6. Synchronization
7. Accounting & Billing

The flow chart for the work flow for processing of DSPV applications and detailed procedure to be followed at each step is as below;



STAGE -01: APPLICATION REGISTRATION**Non-Subsidy Application****Responsibility:** Consumer**Documents Required:** Nil

- a. The consumer shall click the link of the online portal of the ESCOM as tabulated below;

ESCOM	Portal link
BESCOM	https://SRTPV.BESCOM.org/SRTPV/
GESCOM	https://gescomSRTPV.in/SRTPV/
HESCOM	https://SRTPV.hescom.co.in/SRTPV/
CESC	https://SRTPV.cescmysore.org/
MESCOM	https://SRTPV.mesco.in/SRTPV/

- b. Enter the account id which is printed in the electricity bill. The billing data will be fetched automatically and enter the remaining fields such as proposed solar capacity, type of metering – Net or Gross etc.
- c. The Consumer will be verified through OTP sent to registered mobile number.
- d. For LT domestic consumer, wherein the PPA has been waived off, the **Consent Form** will pop up with the applicable terms & conditions and by agreeing to it the consumer can proceed to the next step.
- e. Pay the application fees online using any one of the payment methods displayed on the screen-**applicable for only non-subsidy application**
- f. Application is considered as registered after payment of application fees.
- g. The consumer must mandatorily enter the bank details and upload the photo of cancelled cheque.
- h. Smart Meter Consent Form: The consumer can also avail the facility of Smart Meter procurement through the DSPV portal under the **Application Info Tab**.

- The consumer should click on "Proceed to Meter Request", select the type of existing meter, choose the phase type, and upload the duly signed copy of the Meter Consent Form.
- Upon clicking the "Agree & Submit" button, a "Meter Procurement Letter" for the DSPV plant will be automatically generated.
- This letter will specify whether the consumer is required to procure one number of smart meter configured bidirectionally to record import/export units (in case of new installations serviced with smart meter) or two numbers: one number of smart meter -unidirectional to record solar generation & one number of bidirectionally configured smart meter (in case of installations serviced with electrostatic meters), along with the applicable terms and conditions.
- The consumer shall present the "Meter Procurement Letter" at the ESCOM-authorized smart meter retail outlet to purchase a tested smart meter. The list of authorized retail outlets is available on the DSPV portal.

Subsidy application(PM Surya Ghar Yajana):

- a. At present subsidy is available only for domestic category Consumers who are willing to install solar rooftop plants under PM Surya Ghar Scheme.
- b. For installation of solar rooftop plants under PM Surya Ghar Scheme, the Consumers are required to register their application and apply through National Portal using the link:
<https://www.pmsuryaghar.gov.in/>
- c. Also the consumer can directly click on the link of PM Surya Ghar portal available on ESCOM portal.
- d. Once the application registration process is complete in PM Surya Ghar portal, the Consumers should note down the Registration Reference number generated by the portal for continuing application process in ESCOMs portal.
- e. For continuing the application process in ESCOMs portal, the Consumers are required to click the link displayed at ESCOMs website and enter the Registration Reference number generated by the PM Surya Ghar portal.
- f. Once, the Registration Reference number is entered in ESCOMs portal, the data from PM Surya Ghar portal will be fetched automatically and Consumers will be verified by ESCOMs portal through OTP sent to registered mobile number.

STAGE -02: FEASIBILITY

Responsibility: Sub division

The Category of Consumers for feasibility approval is as below;

- Category –I : Deemed Feasible Applications
- Category – II: Non- Deemed Applications

Category-I:

All DSPV applications with proposed capacity upto 150kW are considered deemed feasible and it is not required to provide feasibility for these applications.

Category-II:

- a) Feasibility shall be provided by sub divisions for all DSPV applications of capacity more than 150 kW.
- b) For providing the feasibility, the designated officer shall visit the proposed DSPV installation premises and verify technical details and shall issue feasibility report.
- c) The procedure for providing feasibility is as below;
 - I. The Sub Division office has to login to the online portal using their login credentials.
 - II. The list of applications for which feasibility is to be provided will be displayed.
 - III. Select one application at a time, open the feasibility tab and enter the required details.
 - IV. After entry of required data in the portal, Feasibility report will be generated automatically.
 - V. Download the feasibility report, sign it and upload it.
- d) The technical feasibility shall be provided in accordance with the following;

- i. Every DSPV plant of less than 150 kW capacity shall be connected only to the existing distribution transformer through which the eligible consumers are being supplied electricity. In such cases, the total capacity of the existing and proposed DSPV plants on that distribution transformer shall not exceed 80% of the rated capacity. This applicable only for LT installations.

Note: If a LT consumer requests for installation of solar rooftop plant of capacity more than 150 kW, the consumer shall convert to HT system i.e., the billing meter shall be HT meter with metering cubicle and solar generation meter will be 3 phase LT CT Operated meter (For net meter arrangement only).

- ii. Every DSPV plant of more than 150 kW shall be connected only to the existing 11 kV distribution system. In such cases, the total capacity of the existing and proposed DSPV plants shall be limited so that line current does not exceed 80 % of the rated current capacity of the line. This applicable only for HT installations

Note: If a HT consumer requests for installation of solar rooftop plant of capacity more than 150 kW, the billing meter shall be bi-directional HT meter and solar generation meter will be 3 phase LT CT Operated meter (For net meter arrangement only).

- iii. If the application is not technically feasible, the SDO shall cancel the Application and intimate the same to the Applicant.

- e) For HT installations, if the existing metering system is 3 phase 3 wire, it shall be converted to 3 phase 4 wire.
- f) Metering cubicle replacement and meter replacement to be indicated in feasibility report. It shall form a part of feasibility report. The existing meter shall be checked and suitable meter change shall be recorded in feasibility report in accordance with following table;

Table No.8

Sl. No	Sanctioned Load	Smart meter (Billing Meter)	Solar Rooftop Plant Capacity	Smart Meter (Solar Generation Meter)	Inverter Type
1	1kW to 35kW	1 Phase or 3 phase	1kWp to 35kWp	1 Phase or 3 phase	1 Phase or 3 phase
2	More than 35 kW up to 50 Kwp	3 phase CT PT Operated meter	More than 50 kWp	3 phase LT CT Operated meter	3 phase

For More than 50kWp:**Table No.9**

Sl. No	Sanctioned Load	Bi-directional Meter (Billing Meter)	Solar Rooftop Plant Capacity	Uni-directional Meter (Solar Generation Meter)	Inverter Type
1	More than 50 kW & upto 150 kW	3 phase LT CT Operated meter	More than 50 kWp & upto 150 kWp	3 phase LT CT Operated meter	3 phase
2	More than 150kW	3 phase CT PT Operated HT meter	More than 150 kWp	3 phase LT CT Operated meter	3 phase

STAGE -03 – EXECUTION OF POWER PURCHASE AGREEMENT (PPA)

Responsibility: Consumer & O&M AEE /EE

The execution of PPA is not applicable for LT Domestic Consumers upto 150kW and the PPA step has been waived off in the online portal.

The Power Purchase Agreement has to be executed in either of the following ways;

- a) Online PPA:1kW to 150kW SRTPV capacities
- b) Offline PPA:>150kW SRTPV Capacities

a) Online PPA:

The online PPA shall be executed by the Consumer for all the DSPV applications which are considered as deemed feasible i.e. for all applications upto 150kW capacity.

The online PPA shall be executed in online mode by the Consumer. The PPA execution is completed only after both the parties i.e. the consumer & concerned ESCOM official have esigned the PPA through online mode.

Note: In case of online PPAs if the consumer has generated the esign link but has not executed within 07 days, the link will be expired and has to approach the ESCOM for re-enabling the link.

The concerned ESCOM officer has to esign the PPA strictly following the timelines

Verification of consumer's esign by the ESCOM officer:

- a) Once the PPAs are esigned by the consumers, the ESCOM officer can double click on the signature box of the consumer which is displayed on the left side at the last page of the PPA.
- b) After double clicking a dialog box is opened which contains the name of the person who has actually signed the PPA.
- c) If the name displayed matches with the name of the RR No. holder or authorized signatory in case of Company or Organization, such PPAs can be esigned by the concerned AEE of C,O&M sub-division ESCOM and the DSPV application can be processed.
- d) If the name displayed does not matches with the name of the RR No. holder, such PPAs are liable to be rejected by the concerned AEE of C,O&M sub-division ESCOM.
- e) In case of joint RR No. holder, if any one RR No. holder esigns the PPA, such PPAs can be accepted and an undertaking/NOC can be obtained from the other RR No. holders of the joint account or the other RR No. holder signature can be obtained manually.

b) Offline PPA:

- The offline PPAs shall be executed for DSPV applications of more than 150kW capacity. The PPAs are to be executed on Rs. 500 value non-judicial stamp paper in Commission approved format.
- The Consumer shall co-ordinate with designated ESCOM officer for PPA execution.
- The PPAs shall be uploaded in the online DSPV portal by designated officers for auto generation of work approval letter.

The Power Purchase Agreement (PPA) Execution Authorities on behalf of ESCOMs for DSPV installations are as tabulated below;

Table No.10

Sl. No.	DSPV plant Capacity	PPA Execution Authority
1	From 1kWp to 500kWp	Assistant Executive Engineer(Ele) , O & M Sub-Division
2	Above 500kWp	Executive Engineer(Ele), O & M Division

PPA Approval Authority:

- I.** For capacities upto 500kWp, Assistant Executive Engineer(Ele) of O & M Sub-Division is the PPA approval authority.
- II.** For capacities above 500kWp and upto & inclusive of 1000kWp, PPAs shall be approved by Corporate Office of the respective ESCOMs.
- III.** The approval of the KERC shall be obtained for all PPAs of DSPV applications with capacities of above 1000kW.
- IV.** In case of any deviation from the standard format of PPA, the approval for the same shall be obtained from KERC.
- V.** The documents to be submitted alongwith draft PPA for Corporate Office or KERC approval are as follows:
 - Copy of Online DSPV Application & Technical Feasibility Report
 - Latest Electricity Bill
 - DPR clearly specifying the nos. of the panels and capacity of each panel to be installed by the consumer
 - Solar Installation plan

- Landownership Document: Sale Deed/Lease Deed whichever is applicable
- In case of KERC approval, Demand Draft drawn in favor of The Secretary KERC for an amount of Rs.7500 per MW or part thereof contracted capacity. For eg if the proposed solar capacity is 1500kW, the DD of amount Rs.15000/- shall be submitted.
- Certification by the ESCOM whether the consumer is under open access or not.

PPAs for additional capacity installation

If a Consumer requests for installation of additional solar capacity, the present PPA shall be canceled and new PPA shall be executed for 25 years with PPA rate being 90% of PPA tariff or present tariff, whichever is lower,

Note:

- i. In case of additional DSPV capacity, for deciding the PPA authority, the total of already commissioned and proposed plant capacity shall be considered.
- ii. If the tariff rate of the DSPV plant has been reduced due to one or the other reasons such as delay in commissioning, change in sanctioned load or additional solar capacity, there shall be no subsequent reduction in the tariff rate.

Intimation for change of HT Metering Cubicle:

In case, if the change of HT Metering Cubicle is required, the sub division officers shall prepare estimate and intimate to the Consumer the supervision charges to be paid, within 07 days of PPA execution.

STAGE -04 – WORK APPROVAL INTIMATION

Responsibility: Sub division

- a. Work approval intimation shall be auto generated and emailed to registered email after online execution of PPA/Uploading of PPA document in case of off-line PPA.
- b. The work approval intimation shall also include intimation for change of meter and if required change of HT metering cubicle.

Note: For LT Domestic Consumers upto 150kW, the work approval will be autogenerated after the registration of the application.

STAGE -05 – WORK COMPLETION INTIMATION**Responsibility:** Consumer

- a) The Consumer shall upload the Work Completion details in online DSPV portal for enabling the sub division offices to process the application for synchronization.
- b) The capacity tolerance allowed in the PV panel capacity is as below:

Table No.11

DSPV capacity & Sanctioned Load	DC Capacity Tolerance	
DSPV up to & including 10 kW	Up to 10% tolerance for DC capacity is allowed. No SPPA required.	For more than 10% variation, the sanctioned load has to increased before commissioning.
Non-Domestic above 10 kW	Any variation between solar proposed and actual capacity, the SPPA for capacity variation to be executed	

- c) The concerned ESCOM authority will be intimated through the SMS to the official mobile number for synchronization of the said DSPV plant.
- d) In case of any observation found by ESCOM official while inspection, the remark shall be entered and work completion report to be returned back to the consumer through the portal.

Note:

In case of subsidy applications, the vendor has to upload the work completion details in MNRE portal and the same details will be auto-fetched to the ESCOM portal. The same details should be verified by the consumer and submit for synchronization.

STAGE -06 – MT INSPECTION REPORT(>17.5kW)

Responsibility: MT AEE (>35kW & <500kW)
MT EE (>500kW).

Note: The synchronization page for solar proposed capacity above 35kW shall be enabled only after the MT inspection report has been updated by the concerned MT officer.

STAGE -07 – SYNCHRONIZATION/Spot SYNCHRONIZATION :

Responsibility: Consumer & ESCOM O&M AEE/EE and MT staff.

- The DSPV plant Commissioning & Synchronizing Authority:

Table No.12

Sl. No.	DSPV Plant Capacities	ESCOM Officers authorized for synchronization
1	1kW upto 35kW with smart meter	Assistant Executive Engineer(Ele), O & M Sub-Division and MT staff not required.
2	Above 35kW upto 50kWp with smart meter	Assistant Executive Engineer(Ele), O & M Sub-Division in co-ordination with Meter Testing (MT) staff.
3	Above 50kW upto 500kWp static meter	Assistant Executive Engineer(Ele) O & M Sub-Division in Co-ordination with Meter Testing (MT) staff
4	Above 500kWp static meter	Executive Engineer(Ele) O & M Division in Co-ordination with Meter Testing (MT) staff

The synchronization certificate shall be generated by Division/Sub Division Officers in the online portal as per DSM Section, BESCO circular dated:05.06.2025

Note:

- For subsidy applications, after synchronization in ESCOM portal, the AEE of C,O&M sub-division should mandatorily complete Inspection Approval in the MNRE portal as per the MNRE guidelines.**
- The application can either be submitted for subsidy release, returned for correction or reject the application.**

II. ACCOUNTING & BILLING

Responsibility: AEE, AE (Technical) & AAO of the sub division

- Login credentials have been created for the AOs & AAOs wherein the concerned officer can login and obtain the required documents such as PPA, synchronization certificate etc required for billing.
- The AAO of the sub division shall ensure that all the DSPV installations synchronized in a calendar month are read and billed in the next calendar month without fail by verifying the details in online portal.
- No hard copies of the documents**, except for PPA in case of offline PPA, shall be collected from Consumer / Installer. If required, documents shall be downloaded by AE(T)/AAO using their login credentials.

**III. TIMELINES:
For 1KW to 150KW:**

Activity	Responsibility	Timeline
Submission of Application which includes PPA(PPA not applicable for LT Domestic consumers up to 150kw). No separate PPA is required to be executed. The submission of application is deemed to be the approval to commence the work.	Consumer/ Distribution Licensee	Zero Date
Online uploading of work Completion Report by the consumer.	Consumer	150(one hundred and fifty) days from the date of uploading/submission of application.
Inspection by ESCOM officials for commission the project, after receipt of work completion report from the consumer.	Distribution Licensee	Within 5(five) working days from the receipt of work completion report, after ensuring satisfactory completion of work. If the plant is not commissioned within 5days from the date of work completion report, the concerned officer shall be liable to pay penalty of Rs.1000 per day, till the date of commissioning, to the applicant. After five days of work completion, in case the plant is not commissioned, the consumer are entitled to deemed generation benefit.
Commissioning of Distributed Solar PV System in case work completion is delayed by the consumer	Consumer/Dist ribution Licensee	In Case of delay of more than six months, the tariff payable will be as per the terms of PPA/application.
Billing process	Distribution Licensee	30 Days from the date of commissioning of the solar plant.
Activity	Responsibility	Timeline

For above 150KW up to Sanctioned load :


Submission of Application Online.	Consumer	Zero Date.
Acknowledgement of Application by distribution licensee ESCOM.	ESCOM	Within 3(three) working days from zero date.
Site verification/ technical Feasibility & Issuance of Letter of Approval/Rejection of application	ESCOM	Within 10(ten) working days from the date of acknowledging the application.
Execution of PPA (including countersignature by the controlling officer up to and inclusive of 1000kw DSPV projects).	ESCOM & CONSUMER	Within 5(five) working days from the date of issuance of Letter of Approval.
Submission for Approval of the PPA to the ESCOM, less than 1000KW And to Commission ,for more than 1000Kw.	ESCOM	Within 07(seven) working days from the date of execution of PPA.
Submission of Works Completion Report by the Consumer.	Consumer	150(one hundred and fifty) days from the date of execution of PPA
Inspection by ESCOM official for commissioning the project, after receipt of work completion report from the consumer	ESCOM	<p>Within 5(Five) working days from the receipt of work completion report after ensuring satisfactory completion of work</p> <p>If the plant is not commissioned within 5 days from the date of work completion report, the concerned officer shall be liable to pay penalty of Rs.1000 per day, till the date of commissioning, to the applicant.</p> <p>After five days of work completion, in case the plant is not commissioned the consumer are entitled to deemed generation benefit.</p>
Commissioning of Distributed solar PV system in case of delay in submission of work completion report by the consumer.	Consumer/ESCOM	In case of delay of more than 6 months, the tariff payable will be as per the terms of PPA.
Billing Process	ESCOM	30 days from the date of commissioning of the solar plant.

Schematic Diagrams:


The Schematic Diagram for Net & Gross Metering arrangement is as below and same arrangement shall be ensured at the time of synchronization.

A. Net Metering Diagrams:

Single Line Diagram of Rooftop Facility for Net Metering Interconnection (LT consumers)




Single Line Diagram of DSPV for HYBRID System (LT Consumers upto 150 kW)




B. Gross Metering Arrangement:

Schematic Diagram of Rooftop Facility for Gross Metering Interconnection




Domestic Consumer Simplified Workflow (Feasibility and PPA Waived Off)

Registration Step



Details of the Consumer fetched from billing software:



Enter the solar rooftop details:

The screenshot shows the 'Apply for a New Distributed Solar Photovoltaic (DSPV)' form. The user has entered Account ID/Consumer ID as 0790619000. The form is divided into three main sections: Applicant details, Rooftop system details, and Applicant contact details.

Applicant details:
 Applicant Name: CHANDRASHEKAR IG
 Applicant Address: NO43 SYNO10 SAI SANKALPA L/O KALKERE VILLAGE BANGALORESOLAR NET METERING
 Subdivision code: 140008
 Subdivision Name: E8 Subdivision
 RR Number: 8EEH65581
 Sanctioned Load / Contract demand: 3 kW
 Connection Type: THREE Phase
 Tariff category: Domestic - LT2A

Rooftop system details:
 Solar Proposed in kWp: 3
 Installation Address: NO43 SYNO10 SAI SANKALPA L/O
 Type of Scheme: Own Investment Scheme
 Type of Grid Connectivity: Gross Metering Net Metering
 Type of connection: 3 Phase HT
 PIN code: 560023
 Latitude of the installation: 12.983827253513642
 Longitude of the installation: 77.57536818085937

Applicant contact details:
 Email: mohankrishna176@gmail.com
 Mobile: 7760201254 (OTP will be sent to this Mobile Number)

Consent Form(For LT Domestic Consumers):

The screenshot shows the 'Consent for Net Metering Arrangements / ನೆಟ್ ಮೀಟರಿಂಗ್ ವ್ಯವಸ್ಥೆಗಳಿಗಾಗಿ ಸಮ್ಮತಿ ಪತ್ರ' form. The form is for CHANDRASHEKAR IG, a consumer of BESCOM. The form contains the following text:

CHANDRASHEKAR IG the consumer of BESCOM residing at, hereinafter, referred to as the "Prosumer" is giving consent for the following, who is generating, consuming and injecting the energy.



- The Prosumer intends to connect and operate the Distributed Solar Photo Voltaic (DSPV) system with BESCOM's HT/LT Distribution system for sale of Solar Power to BESCOM, in terms of the "Karnataka Electricity Regulatory Commission (KERC) Order dated: 09.07.2025.
- The Prosumer intends to install a DSPV system of 3 kWp capacity on the existing roof top of the premises, situated at and bearing number RR. No 8EEH65581 in the same premises, under of BESCOM.
- The Prosumer intends to sell the energy, generated from the DSPV system to BESCOM on net metering basis, from the date of commissioning of the DSPV system.


Explanation: the 'Commissioning' means the stage at which the DSPV system starts generating the power for the use by the Prosumer and injects surplus power if any, into the grid.

- BESCOM intends to purchase the energy, generated by such DSPV system, on Net-metering basis, at the tariff determined by the KERC. Now therefore, in consideration of the foregoing premises, the parties, hereto, intending to be legally bound, hereby agree as under:
 - The BESCOM shall pay for the net energy at Rs 3.86 per kWh, as determined by the KERC order dated: 09.07.2025 for term of this agreement.
 - The Prosumer shall commission the project as per KERC / BESCOM Standard Operating Procedure(SOP). If for any reason the date of commissioning is delayed, beyond the date of commissioning agreed. The tariff payable by the BESCOM shall be lower of the:
 - Tariff agreed to in this agreement
 - Any revised tariff, determined by the Commission, prevailing on the date of commissioning
- The Prosumer, shall pay the Electricity tax and other statutory levies, pertaining to DSPV generation, as may be levied from time to time.
- The Prosumer shall not have any claim for compensation, if the Solar power generated by his DSPV system could not be absorbed by the distribution system due to failure of power supply in the grid/distribution system for the reasons, such as line clear, load shedding and line faults, whatsoever.
- This Consent given shall be in force for a period of 25 years from the date of commissioning of the DSPV system as detailed in the BESCOM Standard Operating Procedure (SOP).
- All the disputes between the parties arising out of or in connection with this Consent given shall be first tried to be settled through mutual negotiation. The parties shall resolve the dispute in good faith and in equitable manner. In case of failure to resolve the dispute, either of the parties may approach the appropriate law Forum.


I undertake to abide by the provisions of:

- Central Electricity Authority (Installation and Operation of Meters) Regulations
- Central Electricity Authority (Measures Relating to Safety and Electricity Supply) Regulations
- Karnataka Electricity Regulatory Commission (Implementation of Solar Rooftop PV Systems) Regulations, 2016 and as amended from time to time or any subsequent re-enactment thereof.
- BESCOM Guidelines, and SOP
- Any other relevant Regulations/rules/ GOI/GOK Directions/guidelines issued from time to time





Verification of the consumer by OTP:



Payment of Fees (For Non-Subsidy Consumers)

The screenshot shows the BESCOM SRTPV Online Application form. A modal window titled "Application Received!!" is displayed in the center. The form in the background contains the following details:

- Applicant Name:** CHANDRASHEKAR IG
- Applicant Address:** NO43 SYNO10 SAI SANKALPA L/O KALKERE VILLAGE BANGALORESOLAR NET METERING
- Subdivision code:** 140008
- Subdivision Name:** E8 Subdivision
- RR Number:** 8EEH65581
- Sanctioned Load / Contract demand:** 3 kW
- Connection Type:** THREE Phase
- Tariff category:** Domestic - LT2A
- Solar Proposed in kWp:** 3
- Installation Address:** NO43 SYNO10 SAI SANKALPA L/O
- Type of Scheme:** Own Investment Scheme
- Net Metering:** Net Metering
- Pincode:** 560023
- Latitude of the installation:** 12.983827253513642
- Longitude of the installation:** 77.57536818085937

The "Application Received!!" modal contains the following text:

Thank You. Your Application for Solar Rooftop Installation is with us.

Please note the Reference Number 1000017467 for tracking.

Please complete the payment & e-sign of PPA to complete your Application Registration Process

Registration Charges: Rs. 500
 Facilitation Charges: Rs.1000
 SGST (@9%): Rs.135
 CGST (@9%): Rs.135
 Total: Rs.1770

Buttons: "Continue", "Resend OTP", "Locate Latitude & Longitude on Google Map", "OR Use my current location".

The screenshot shows the BESCOM SRTPV Online Application Tracker page for application number 1000017467. The page displays the following details:

- NET METERING**
- Subdivision code:** 140008
- Subdivision Name:** E8 Subdivision
- RR Number:** 8EEH65581
- Sanctioned Load / Contract demand:** 3.0 kW
- Connection Type:** THREE Phase
- Tariff category:** Domestic - LT2A
- Pincode:** 560023
- Latitude:** 12.983827253513642
- Longitude:** 77.57536818085937

Applicant contact details:

- Email-Id: mohankrishna176@gmail.com
- Mobile Number: 7760201254

Tariff Details:



- Tariff Date: 2025-08-11 11:39:16.0
- Tariff Rate: 3.86
- Tariff Consent: Download Tariff Consent



Bank Details: Submit your Bank Details [Click Here](#)

Status History:

Status	Changed by	Date	Next Action	Pending with	Remarks
Registered. Pending for payment	Applicant	11 Aug 2025 11:39:17 AM	Payment Successful. Pending feasibility	Applicant	

Application Payment Step





Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
PPA Approved and Work Approval Intimated.	E8 Subdivision	11 Aug 2025 12:35:47 PM	Work completion intimated. Pending commission	Applicant	
PPA Submitted.	E8 Subdivision	11 Aug 2025 12:35:46 PM	PPA Approved and Work Approval Intimated.	E8 Subdivision	
Feasibility Completed. Intimated for submitting PPA	E8 Subdivision	11 Aug 2025 12:35:45 PM	PPA Submitted.	Applicant	Auto Feasible
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 12:35:43 PM	Feasibility Completed. Intimated for submitting PPA	E8 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 11:39:17 AM	Payment Successful. Pending feasibility	Applicant	



Map showing location details: KKS Rd, Risaldar St, Crescent Rd, Taj West End, Bengaluru.



BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED
Wholly owned Govt. of Karnataka Undertaking

Summary of SRTPV Application No. 1000017467

Payment Details	
Transaction ID	BHDSFEQ0SYDNUU
Transaction Date	11-Aug-2025 12:35:42 PM
Transaction Reference Number	421953585022
Amount Paid	2.36 (inclusive of taxes)
Taxes (CGST & SGST)	0.3599999999999999
Payment Mode	UPI
Status	Success
Remarks	PGS10001-Success
GSTIN	29AACCB1412G1Z5
GST Service Account Code Number	998631

Application details	Account details
Application No	1000017467
Type of scheme	Own Investment Scheme
Type of Grid connectivity	Net Metering
Solar Proposed in kWp	3.0
Account ID	0790619000
Applicant Name	CHANDRASHEKAR IG
Applicant address	NO43 SYN010 SAI SANKALPA LIO KALKERE VILLAGE BANGALORESOLAR NET METERING





Work Completion Step

Application No. 1000017467 Feasible Solar capacity in kWp : 3.0

The PPA Date : **11-08-2025**

The work of installation of SRTPV system is completed and I would like to submit the following information for your kind needful.

Solar PV Module

Sl No.	Make of the PV Module	Type of the PV Module	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="button" value="Add"/>	<input type="button" value="Delete"/>
Total PV Panel capacity (in kWp)						0		

Inverter

Sl No.	Make of the Inverter	Type of the Inverter	Capacity of the Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="button" value="Add"/>	<input type="button" value="Delete"/>
Total Inverter capacity (in kVA)						0		

Meter Details

Sl. No	Particulars	Main Meter
1	Make	<input type="text"/>
2	Type	<input type="text"/>
3	Sl No.	<input type="text"/>
4	Phase	<input type="text"/>
5	CT Ratio	<input type="text"/>
6	PT Ratio	<input type="text"/>
7	Date of Test by MT Division	<input type="text"/>
8	Meter Testing Report (PDF less than 2 MB)	<input type="button" value="Choose File"/> <input type="button" value="No file chosen"/>

Declaration

I declare that other equipment such as DC/AC Cabels, A/B/DC distribution box, Earthing, DC/AC Surge arrestor are installed as per Technical Specification

System Installer Details

System Installer Firm Name

System Installer Firm GST Number

Work Declaration form (Download here)

BESCOM | SRTPV Online Applica... x BESCOM | SRTPV Online Applica... x +

srtpv.bescom.org/SRTPV_TEST/application_tracker_work_execution.jsp?applicationno=1000017467

DSPV ONLINE SERVICES APPLY ONLINE APPLY ONLINE (SOUBRA GRUHA YOJANE) APPLY ONLINE (GOVT BUILDINGS) VIEW STATUS OFFICERS LOGIN

Application Info **Work Completion** **Commissioning**

Application No. 1000017467 Feasible Solar capacity in kWp : 3.0
 The PPA Date : 11-08-2025

The work of installation of SRTPV system is completed and I would like to submit the following information for your kind needful.

Solar PV Module

Sl No.	Make of the PV Module	Type of the PV Module	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Mono	0.500	6	test01,test02,test03,test0	3	+	-
Total PV Panel capacity (in kWp)						3.000		

Inverter

Sl No.	Make of the Inverter	Type of the Inverter	Capacity of the Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Hybrid	3	1	test01	3	+	-
Total Inverter capacity (in kVA)						3		

Windows taskbar: ENG 12:53 PM US 8/11/2025

BESCOM | SRTPV Online Applica... x BESCOM | SRTPV Online Applica... x +

srtpv.bescom.org/SRTPV_TEST/application_tracker_work_execution.jsp?applicationno=1000017467

Meter Details

Sl. No	Particulars	Main Meter
1	Make	M/s Genus Power Infrastructures Limited
2	Type	SMART METER
3	Sl No.	Test01
4	Phase	Three Phase
5	CT Ratio	0
6	PT Ratio	0
7	Date of Test by MT Division	10/08/2025
8	Meter Testing Report (PDF less than 2 MB)	Choose File Draft_PPA1000656856.pdf

Declaration



I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arrestor are installed as per Technical Specification



System Installer Details

System Installer Firm Name: Test
 System Installer Firm GST Number: Test
 Work Declaration form (Download here): Choose File Esign_PPA_1000017467.pdf

Submit Clear

Windows taskbar: ENG 12:53 PM US 8/11/2025





Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
MT inspection completed. Pending synchronization	Applicant	11 Aug 2025 12:54:53 PM	Synchronized	E8 Subdivision	
PPA Approved and Work Approval Intimated.	E8 Subdivision	11 Aug 2025 12:35:47 PM	Work completion intimated. Pending commission	Applicant	
PPA Submitted.	E8 Subdivision	11 Aug 2025 12:35:46 PM	PPA Approved and Work Approval Intimated.	E8 Subdivision	
Feasibility Completed. Intimated for submitting PPA	E8 Subdivision	11 Aug 2025 12:35:45 PM	PPA Submitted.	Applicant	Auto Feasible
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 12:35:43 PM	Feasibility Completed. Intimated for submitting PPA	E8 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 11:39:17 AM	Payment Successful. Pending feasibility	Applicant	

Map showing location details: For development purposes only, KKS Rd, Risaldar St, 2nd Cross, Crescent Rd, Race Point, Taj West End, Bengal...

Work Execution details of of SRTPV Application No. 1000017467

Solar PV Module

Sl No	Make	Type	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity
1	Test	Mono	0.5	6	test01,test02,test03,test04	3.0

Inverter

Sl No	Make	Type	Capacity of Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity
1	Test	Hybrid	3.0	1	test01	3.0



Bidirectional Main Meter

Make	M/s Genus Power Infrastructures Limited
Type	SMART METER
Serial No	Test01
Phase	Three Phase
CT Ratio	0.0
PT Ratio	0.0
Date of Test by MT division	10 Aug 2025
System Installer Firm Name	Test
System Installer Firm License Number	Test

Certified that the above said SRPTV system was installed by me and the equipment's used comply the Technical and Safety standards issued by BESCOM.

Report submitted on : 11 Aug 2025 12:54:53 PM

Commissioning Step



Inspection Details

Confirm Tariff and Solar Details * Same Tariff and Installed Capacity
 Change in Tariff and Installed Capacity

Installed Capacity
 Applicable Tariff

Pincode
 District of the installation
 Latitude of the installation*
 Longitude of the installation*

Locate Latitude & Longitude on Google Map
 OR Use my current location

Whether Anti-islanding feature is in working condition? * Yes No
 Is DC earthing verified? * Yes No
 Is AC earthing verified? * Yes No
 Is LA earthing verified? * Yes No
 Is AC & DC DB available? * Yes No
 Is Manual Switch on solar side available? * Yes No
 Is Relay operated automatic switch at net-meter side available? * Yes No

Date of Inspection
 Photo of the plant along with the Prosumer (JPEG file < 2 MB) No file chosen
 Date of synchronizing with BESCOM grid
 Synchronization Voltage Level

Remarks not exceeding 1000 characters

Inspection Details

Confirm Tariff and Solar Details * Same Tariff and Installed Capacity
 Change in Tariff and Installed Capacity

Installed Capacity
 Applicable Tariff

Change in Installed Capacity
 Change in Applicable Tariff
 Reason Type:
 Remarks

Pincode
 District of the installation
 Latitude of the installation*
 Longitude of the installation*

Locate Latitude & Longitude on Google Map
 OR Use my current location

Whether Anti-islanding feature is in working condition? * Yes No
 Is DC earthing verified? * Yes No
 Is AC earthing verified? * Yes No
 Is LA earthing verified? * Yes No
 Is AC & DC DB available? * Yes No
 Is Manual Switch on solar side available? * Yes No
 Is Relay operated automatic switch at net-meter side available? * Yes No

Date of Inspection
 Photo of the plant along with the Prosumer (JPEG file < 2 MB) No file chosen
 Date of synchronizing with BESCOM grid
 Synchronization Voltage Level

Remarks not exceeding 1000 characters

Confirm Tariff and Solar Details * Same Tariff and Installed Capacity Change in Tariff and Installed Capacity

Installed Capacity: 3.0
 Applicable Tariff: 3.86

Change in Installed Capacity:
 Change in Applicable Tariff:

Reason Type: **Select Reason** (dropdown menu open)

Remarks:
 Dist:
 Latitude:
 Longitude:

Locate Latitude & Longitude on Google Map
 OR **Use my current location**

Whether Anti-islanding feature is in working condition? Yes No
 Is DC earthing verified? Yes No
 Is AC earthing verified? Yes No
 Is LA earthing verified? Yes No
 Is AC & DC DB available? Yes No
 Is Manual Switch on solar side available? Yes No
 Is Relay operated automatic switch at net-meter side available? Yes No

Date of Inspection:
 Photo of the plant along with the Prosumer (JPEG file < 2 MB): Choose File No file chosen
 Date of synchronizing with BESCOM grid:
 Synchronization Voltage Level:

Remarks not exceeding 1000 characters:

[Return to Work Completion](#) [Submit](#)

which ever is later.
 6. The other norms of the SRTPV tariff order / Regulation issued from time to time is applicable.

Work Declaration Details [Download](#)

Meter Information

Bi-Direction Meter (Main)*				Existing Meter*	
Meter make:	M/s Genus Power Infrastruct			Test	
Meter phase:	Three Phase			Three Phase	
Meter Type:	SMART METER			SMART METER	
Serial number:	Test01			TEST01	
Meter constant:	0.0			1	
Initial reading (Tri vector parameters) Import:	20			20	
Initial reading (Tri vector parameters) Export:	20			20	

Solar PV Module

Sl. No.	Make of the PV Module	Type of the PV Module	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Mono	0.5	6	test01,test02,te	3.0	+	-

Total PV Panel capacity (in kWp) 3.0

Grid Tied Inverter

Sl. No.	Make of the Inverter	Type of the Inverter	Input voltage (volts)	Output voltage (volts)	Capacity of the Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Hybrid	220	220	3.0	1	test01	3.0	+	-

Total Inverter capacity (in kVA) 3.0

Inspection Details

Confirm Tariff and Solar Details * Same Tariff and Installed Capacity
 Change in Tariff and Installed Capacity

Installed Capacity: 3.0
Applicable Tariff: 3.86

Pincode: 560023
District of the installation: 525,BENGALURU URBAN
Latitude of the installation*: 12.983827253513642
Longitude of the installation*: 77.57536818085937

Locate Latitude & Longitude on Google Map
OR Use my current location

Whether Anti-islanding feature is in working condition? * Yes No
Is DC earthing verified? * Yes No
Is AC earthing verified? * Yes No
Is LA earthing verified? * Yes No
Is AC & DC DB available? * Yes No
Is Manual Switch on solar side available? * Yes No
Is Relay operated automatic switch at net-meter side available? * Yes No

Date of Inspection: 10/08/2025
Photo of the plant along with the Prosumer (JPEG file < 2 MB): Choose File | IMG-2...001.jpg
Date of synchronizing with BESCOM grid: 11/08/2025
Synchronization Voltage Level: 220

Synchronized: _____

srtpv.bescom.org says
Please confirm the details entered. Do you wish to continue ?



Pincode: 560023
District of the installation: 525,BENGALURU URBAN
Latitude of the installation*: 12.983827253513642
Longitude of the installation*: 77.57536818085937

Locate Latitude & Longitude on Google Map
OR Use my current location

Whether Anti-islanding feature is in working condition? * Yes No
Is DC earthing verified? * Yes No
Is AC earthing verified? * Yes No
Is LA earthing verified? * Yes No
Is AC & DC DB available? * Yes No
Is Manual Switch on solar side available? * Yes No
Is Relay operated automatic switch at net-meter side available? * Yes No

Date of Inspection: 10/08/2025
Photo of the plant along with the Prosumer (JPEG file < 2 MB): Choose File | IMG-2...001.jpg
Date of synchronizing with BESCOM grid: 11/08/2025
Synchronization Voltage Level: 220

Synchronized: _____



Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
Synchronized	EB Subdivision	11 Aug 2025 01:58:00 PM	null		Synchronized
MT Inspection completed. Pending synchronization	Applicant	11 Aug 2025 12:54:53 PM	Synchronized	EB Subdivision	
PPA Approved and Work Approval Intimated.	EB Subdivision	11 Aug 2025 12:35:47 PM	Work completion Intimated. Pending commission	Applicant	
PPA Submitted.	EB Subdivision	11 Aug 2025 12:35:46 PM	PPA Approved and Work Approval Intimated.	EB Subdivision	
Feasibility Completed. Intimated for submitting PPA	EB Subdivision	11 Aug 2025 12:35:45 PM	PPA Submitted.	Applicant	Auto Feasible
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 12:35:43 PM	Feasibility Completed. Intimated for submitting PPA	EB Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 11:39:17 AM	Payment Successful. Pending feasibility	Applicant	

BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED
Wholly owned Govt. of Karnataka Undertaking

Commissioning details of SRTPV Application No. 1000017467

Meters

Sl No	Make	Type	Capacity of each module (kWh)	No. of modules	Sl. No of modules (Comma separated)	Total capacity of this make, type & capacity
1	Test	Mono	0.5	6	test01.test02.test03.test04	3.0


Solar PV Panels

Sl No	Make	Type	Input Voltage	Output Voltage	Capacity of Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity
1	Test	Hybrid	220.0	220.0	3.0	1	test01	3.0

Inverter


Is Anti-Islanding feature Available ?	Yes
Is DC earthing verified ?	Yes
Is AC earthing verified ?	Yes
Is LA earthing verified ?	Yes
Is AC & DC DB available ?	Yes
Is Manual Switch on solar side available ?	Yes
Is Relay controlled automatic switch at net meter side available ?	Yes
Date of Inspection	10 Aug 2025
Date of Synchronization to BESCOM grid	11 Aug 2025
Synchronization Voltage Level	220

Report submitted on : 11 Aug 2025 01:57:40 PM



Above 150Kw Workflow

Registration Step



DSPV ONLINE SERVICES APPLY ONLINE APPLY ONLINE (SOURA GRUHA YOJANE) APPLY ONLINE (GOVT. BUILDINGS) VIEW STATUS OFFICERS' LOGIN

Apply for a New Distributed Solar Photovoltaic (DSPV)

Enter your Account ID/Consumer ID to proceed:

Applicant details

Applicant Name: M/S TRIDENT AUTOMOBILES PVT LT
 Applicant Address: CAR SHOWROOMNAGANATHAPURA
 Subdivision code: 140125
 Subdivision Name: S20 Subdivision
 RR Number: S8HT274
 Sanctioned Load / Contract demand: 250 kVA
 Connection Type: THREE Phase
 Tariff category: Commercial - HT2b

Rooftop system details

Solar Proposed in kWp*

Installation Address*

Type of Scheme* --Select Scheme--
 Multiple Generation Meter* Yes No
 Type of Grid Connectivity* Gross Metering Net Metering
 Type of connection*

PIN code*

Latitude of the installation*

Longitude of the installation*

[Locate Latitude & Longitude on Google Map](#)
 OR Use my current location

Applicant contact details

Email* Mobile* (OTP will be sent to this Mobile Number)

DSPV ONLINE SERVICES APPLY ONLINE APPLY ONLINE (SOURA GRUHA YOJANE) APPLY ONLINE (GOVT. BUILDINGS) VIEW STATUS OFFICERS' LOGIN

Apply for a New Distributed Solar Photovoltaic (DSPV)

Enter your Account ID/Consumer ID to proceed:

Applicant details

Applicant Name: M/S TRIDENT AUTOMOBILES PVT LT
 Applicant Address: CAR SHOWROOMNAGANATHAPURA
 Subdivision code: 140125
 Subdivision Name: S20 Subdivision
 RR Number: S8HT274
 Sanctioned Load / Contract demand: 250 kVA
 Connection Type: THREE Phase
 Tariff category: Commercial - HT2b

Rooftop system details

Solar Proposed in kWp*

Application for Multiple Installations in the same premise

Installation Address* SHOWROOMNAGANATHAPURA

Type of Scheme* Own Investment
 Multiple Generation Meter* Yes No
 Type of Grid Connectivity* Gross Metering Net Metering
 Type of connection* 3 Phase HT
 PIN code* 560023
 Latitude of the installation* 12.983492708088045
 Longitude of the installation* 77.57777144013671

[Locate Latitude & Longitude on Google Map](#)
 OR Use my current location

Applicant contact details

Email* Mobile* (OTP will be sent to this Mobile Number)

srtpv.bescom.org says
Please confirm the details entered. Do you wish to continue ?

OK Cancel

Apply for a New Distributed Solar Photovoltaic (DSPV)

Enter your Account ID/Consumer ID to proceed 0170996000 Fetch details

Applicant details

Applicant Name: M/S TRIDENT AUTOMOBILES PVT LT
Applicant Address: CAR SHOWROOMNAGANATHAPURA
Subdivision code: 140125
Subdivision Name: S20 Subdivision
RR Number: S8HT274
Sanctioned Load / Contract demand: 250 kVA
Connection Type: THREE Phase
Tariff category: Commercial - HT2b

Rooftop system details

Solar Proposed in kWp* 160
 Application for Multiple Installations in the same premise
Installation Address* SHOWROOMNAGAN ATHAPURA
Type of Scheme* Own Investment
Multiple Generation Meter* Yes No
Type of Grid Connectivity* Gross Metering Net Metering
Type of connection* 3 Phase HT
PIN code* 560023
Latitude of the installation* 12.983492708088045
Longitude of the installation* 77.57777144013671
[Locate Latitude & Longitude on Google Map](#)
[OR Use my current location](#)

Applicant contact details

Email* mohankrishna176@gmail.com Mobile* 7760201254 (OTP will be sent to this Mobile Number) Send OTP

srtpv.bescom.org says
OTP is generated and sent to mobile number. Please enter

OK

Enter your Account ID/Consumer ID to proceed 0170996000 Fetch details

Applicant details

Applicant Name: M/S TRIDENT AUTOMOBILES PVT LT
Applicant Address: CAR SHOWROOMNAGANATHAPURA
Subdivision code: 140125
Subdivision Name: S20 Subdivision
RR Number: S8HT274
Sanctioned Load / Contract demand: 250 kVA
Connection Type: THREE Phase
Tariff category: Commercial - HT2b

Rooftop system details

Solar Proposed in kWp* 160
 Application for Multiple Installations in the same premise
Installation Address* SHOWROOMNAGAN ATHAPURA
Type of Scheme* Own Investment
Multiple Generation Meter* Yes No
Type of Grid Connectivity* Gross Metering Net Metering
Type of connection* 3 Phase HT
PIN code* 560023
Latitude of the installation* 12.983492708088045
Longitude of the installation* 77.57777144013671
[Locate Latitude & Longitude on Google Map](#)
[OR Use my current location](#)

Applicant contact details

Email* mohankrishna176@gmail.com Mobile* 7760201254 (OTP will be sent to this Mobile Number) Send OTP

Applicant details

Applicant Name: M/S TRIDENT AUTOMOBILES PVT LT
 Applicant Address: CAR SHOWROOMNAGANATHAPURA
 Subdivision code: 140125
 Subdivision Name: S20 Subdivision
 RR Number: S8HT274
 Sanctioned Load / Contract demand: 250 KVA
 Connection Type: THREE Phase
 Tariff category: Commercial - HT2b

Rooftop system details

Solar Proposed in kWp: 160
 Application for Multiple Installations in the same premise
 Installation Address: SHOWROOMNAGANATHAPURA
 Type of Scheme: Own Investment
 Multiple Generation Meter: Yes No
 Type of Grid Connectivity: Gross Metering Net Metering
 Type of connection: 3 Phase HT
 PIN code: 560023
 Latitude of the installation: 12.983492708088045
 Longitude of the installation: 77.57777144013671
[Locate Latitude & Longitude on Google Map](#)
[OR Use my current location](#)

Applicant contact details

Email: mohankrishna176@gmail.com Mobile: 7760201254 [Send OTP](#)
 (OTP will be sent to this Mobile Number)
 Verify OTP: 1254 [Verify & Proceed](#)

Application Received !!

Thank You. Your Application for Solar Rooftop Installation is with us.

Please note the Reference Number 1000017513 for tracking.

Please complete the payment to complete your Application Registration Process

Registration Charges: Rs. 5000
 Facilitation Charges: Rs.10000
 SGST (@9%): Rs.1350
 CGST (@9%): Rs.1350
 Total: Rs.17700

[Continue](#)

0816, 080 2234 0817 solar_helpdesk@bescom.co.in

Application Info Feasibility PPA Work Completion Commissioning

Application No. 1000017513 [Cancel the application](#)

1. Application Details 2. Payment Details

Applicant details

Account ID: 0170996000

Applicant Name: M/S TRIDENT AUTOMOBILES PVT LT

Applicant Address: CAR SHOWROOMNAGANATHAPURA

Subdivision code: 140125

Subdivision Name: S20 Subdivision

RR Number: SBHT274

Sanctioned Load / Contract demand: 250.0 KVA

Connection Type: THREE Phase

Tariff category: Commercial - HT2b

Proposed Rooftop system details

Type of Scheme: Own investment

Type of Grid Connectivity: Net Metering [Edit](#)

Solar Proposed in kWp: 160.0 [Edit](#)

Type of connection: 3 Phase HT

Pincode: 560023

Latitude: 12.983492708088045

Longitude: 77.57777144013671

Applicant contact details

Email-Id: mohankrishna176@gmail.com

Mobile Number: 7760201254

Bank Details

Submit your Bank Details

[Click Here](#)


Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
Registered. Pending for payment	Applicant	11 Aug 2025 02:51:54 PM	Payment Successful. Pending feasibility	Applicant	

Map showing location: Race Course Rd, Bengaluru. Includes a green circular area representing the rooftop system.

© 2020 - Design By BESCOM 080 2234 0816 solar_helpdesk@bescom.co.in



Application Payment Step



Bangalore Electricity Supply Company Limited

<p>Payment Methods</p> <ul style="list-style-type: none"> Credit / Debit Cards > Net Banking > UPI > BHIM Instant Cashback upto Rs. 50 > QR > 	<p>Cards</p> <p style="text-align: center;"></p> <p>Card Number <input type="text"/></p> <p>Expiration Date <input type="text"/> / <input type="text"/> <small>MM/YY</small> CVV/CVC <input type="text"/></p> <p>Card Holder Name <input type="text"/></p> <p style="text-align: center; background-color: #f4a460; color: white; padding: 5px; border-radius: 5px;">Make Payment for ₹2.36</p>	<p>Merchant Name ×</p> <p>Bangalore Electricity Supply Company Limited</p> <p>Order Id</p> <p>918386016552</p> <p>Payment Amount ₹2.36</p> <p style="text-align: right;"> BillDesk</p> <p style="text-align: right; font-size: small;">Privacy Policy Terms & Conditions</p>
---	--	--





Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 02:57:52 PM	Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 02:51:54 PM	Payment Successful. Pending feasibility	Applicant	

The map shows the application location in Bangalore, Karnataka, near Race Course Rd and Anand Rao Circle Police Quarters. The map includes a red location pin and various street names.

Footer: @ 2020 - Design By BESCOM | 080 2234 0816 | solar_helpdesk@bescom.co.in

BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED
Wholly owned Govt. of Karnataka Undertaking

Summary of SRTPV Application No. 1000017513

Payment Details	
Transaction ID	BHDSCHF0S2CCVH
Transaction Date	11-Aug-2025 02:57:51 PM
Transaction Reference Number	19270056128
Amount Paid	238 (inclusive of taxes)
Taxes (CGST & SGST)	0.3599999999999999
Payment Mode	UPI
Status	Success
Remarks	PGS10001-Success
GSTIN	29AACCB1412G1Z5
GST Service Account Code Number	988631

Application details		Account details	
Application No.	1000017513	Account ID	0170949000
Type of scheme	Own investment	Applicant Name	M/S TRIDENT AUTOMOBILES PVT LT
Type of Grid connectivity	Net Metering	Applicant address	CAR
Solar Proposed in kWp	160.0	City	SHOWROOMNAGANATHAPURA
Minimum Shadow free area in Sq. mtr	1.0	Pincode	
Type of connection	3 Phase HT	Subdivision code	140125
DIN		Subdivision Name	S20 Subdivision
Audhar Number		RR Number	SH1274
Pin code	960023	Sanctioned Load	290.0 kVA
Latitude	12.98349270888043	Connection Type	THREE Phase
Longitude	77.87777144013671	Tariff category	Commercial - HT2b
MNRE Subsidy sanctioned or not?	No		
Wish to avail MNRE Subsidy?	No		
Registered Date	11-Aug-2025 02:51:54 PM		

Application_1000017513_11082025_145154.pdf 2 / 2 56%

Minimum shadow free area in Sq. mtr	1.0	City	SHOWROOMMAGANATHAPURA
Type of connection	3 Phase HT	Pincode	
PAN		Subdivision code	140125
Eachar Number		Subdivision Name	S20 Subdivision
Pin code	560023	RR Number	SBR274
Latitude	12.98349270868045	Sanctioned Load	250.0 KVA
Longitude	77.5777144013671	Connection Type	THREE Phase
MNRE Subsidy sanctioned or not?	No	Tariff category	Commercial - HT25
Wish to avail MNRE Subsidy?	No		
Registered Date	11-Aug-2025 02:51:54 PM		

Applicant contact details

Email Id	mohankrishna176@gmail.com
Mobile Number	7760201254

This is a system generated letter and doesn't require signature

Feasibility Step

BESCOM DSPV ONLINE SERVICES ASSISTANT EXECUTIVE ENGINEER(EL), S20 SUBDIVISION LOGOUT

Application No. 1000017513 (Proposed Solar capacity in kWp : 160.0)

Distribution Transformer Information

DTC location*

DT Code*

DT Capacity in kVA*

Connected Load on DT in kW*

S RTPV capacity already connected in kWp*

S RTPV capacity under progress in kWp*

Feeder Information

Substation Name*

Feeder Name*

Feeder MDM Code

Feeder conductor size in sq mm*

Rated current carrying capacity in Amps*

S RTPV capacity already connected in Amps*

S RTPV capacity under progress in Amps*

S RTPV capacity proposed in Amps*

Feasibility

Feasible Partially Feasible Not Feasible

Remarks not exceeding 1000 characters

Download/Upload

[Download Unsigned Feasibility Report](#)

Signed Feasibility Report (PDF < 2MB)

(Feasibility is complete only after downloading the unsigned feasibility report and uploading a signed copy of the same)

DSPV ONLINE SERVICES ASSISTANT EXECUTIVE ENGINEER(ELE), 630 SUBDIVISION LOGOUT

Application No. 1000017513 (Proposed Solar capacity in kWp : 160.0)

Distribution Transformer Information

DTC location* Test
 DT Code* Test01
 DT Capacity in kVA* 1000
 Connected Load on DT in kW* 100
 SRTPV capacity already connected in kWp* 10
 SRTPV capacity under progress in kWp* 10

Feeder Information

Substation Name* HSRLAYOUT_220
 Feeder Name* F01-BOMMANAHAI
 Feeder MDM Code 1110303904010101
 Feeder conductor size in sq mm* 1
 Rated current carrying capacity in Amps* 1
 SRTPV capacity already connected in Amps* 1
 SRTPV capacity under progress in Amps* 1
 SRTPV capacity proposed in Amps* 1

Feasibility

Feasible Partially Feasible Not Feasible
 SRTPV is Feasible

Download/Upload

Download Unsigned Feasibility Report
 Signed Feasibility Report (PDF < 2MB)

Submit
 (Feasibility is complete only after downloading the unsigned feasibility report and uploading a signed copy of the same)

DSPV ONLINE SERVICES ASSISTANT EXECUTIVE ENGINEER(ELE), 630 SUBDIVISION LOGOUT

Application No. 1000017513 (Proposed Solar capacity in kWp : 160.0)

Distribution Transformer Information

DTC location* Test
 DT Code* Test01
 DT Capacity in kVA* 1000
 Connected Load on DT in kW* 100
 SRTPV capacity already connected in kWp* 10
 SRTPV capacity under progress in kWp* 10

Feeder Information

Substation Name* HSRLAYOUT_220
 Feeder Name* F01-BOMMANAHAI
 Feeder MDM Code 1110303904010101
 Feeder conductor size in sq mm* 1
 Rated current carrying capacity in Amps* 1
 SRTPV capacity already connected in Amps* 1
 SRTPV capacity under progress in Amps* 1
 SRTPV capacity proposed in Amps* 1

Feasibility

Feasible Partially Feasible Not Feasible
 Feasible capacity in kWp 120
 SRTPV is Partially Feasible for 120 kWp

Download/Upload

Download Unsigned Feasibility Report
 Signed Feasibility Report (PDF < 2MB)

Submit
 (Feasibility is complete only after downloading the unsigned feasibility report and uploading a signed copy of the same)

DSPV ONLINE SERVICES ASSISTANT EXECUTIVE ENGINEER(ELE), S20 SUBDIVISION LOGOUT

Application No. 1000017513 (Proposed Solar capacity in kWp : 160.0)

Distribution Transformer Information

DTC location* Test
 DT Code* Test01
 DT Capacity in kVA* 1000
 Connected Load on DT in kW* 100
 SRTPV capacity already connected in kWp* 10
 SRTPV capacity under progress in kWp* 10

Feeder Information

Substation Name* HSRLAYOUT_220
 Feeder Name* F01-BOMMANAHAI
 Feeder MDM Code 1110303904010101
 Feeder conductor size in sq mm* 1
 Rated current carrying capacity in Amps* 1
 SRTPV capacity already connected in Amps* 1
 SRTPV capacity under progress in Amps* 1
 SRTPV capacity proposed in Amps* 1

Feasibility

Feasible Partially Feasible Not Feasible
 SRTPV is not Feasible. Application will be cancelled.

Download/Upload

Download Unsigned Feasibility Report
 Signed Feasibility Report (PDF < 2MB)

Submit

(Feasibility is complete only after downloading the unsigned feasibility report and uploading a signed copy of the same)

Application_Feasibility_1000017513_11082025_151420.pdf 1 / 1 67%

BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED
 Wholly owned Govt. of Karnataka Undertaking

Ref: Office of the Assistant Executive Engineer(Ele),
 S20 subdivision, BESCOM, Agara, Bengaluru



Feasibility Report for SRTPV Application No. 1000017513
 Proposed solar capacity: 160.0



DT Information		Feeder Information	
DTC Location	Test	Substation Name	HSRLAYOUT_220
DT Code	Test01	Feeder Name	F01-BOMMANAHALLI-IND
DT Capacity in kVA	1000.0	Feeder MDM code	1110303904010101
Connected Load on DT in kW	100.0	Feeder conductor size in sq. mm	1.0
SRTPV Capacity already connected in kWp	10.0	Rated current carrying capacity in Amps	1.0
SRTPV Capacity under progress in kWp	10.0	SRTPV capacity already connected in Amps	1.0
		SRTPV capacity under progress in Amps	1.0
		SRTPV capacity proposed in Amps	1.0

Feasibility	
Proposed Application is	Feasible
Allowable SRTPV Capacity	160.0
Remarks	SRTPV is Feasible.

Assistant Executive Engineer(Ele)
 S20 Subdivision, BESCOM

Report generated on 11 Aug 2025 03:14:39 PM





The screenshot shows a web browser window with the URL srtpv.bescom.org/SRTPV_TEST/application_tracker_application_info.jsp?applicationno=1000017513. The page displays a 'Status History' table and a map of the application location.

Status	Changed by	Date	Next Action	Pending with	Remarks
Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	11 Aug 2025 03:17:30 PM	PPA Submitted.	Applicant	SRTPV is Feasible.
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 02:57:52 PM	Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 02:51:54 PM	Payment Successful. Pending feasibility	Applicant	

The map below the table shows the application location on a street grid, with a red pin and a green circular area indicating the site. The map includes labels for 'ANAND RAO CIRCLE POLICE QUARTERS' and 'Race Course Rd'.



PPA Step



The screenshot shows the 'PPA' step of the application process. The page title is 'DSPV ONLINE SERVICES' and the user is logged in as 'ASSISTANT EXECUTIVE ENGINEER/ELE, S20 SUBDIVISION'. The application number is 1000017513, and the feasible solar capacity is 160.0 kWp.



The 'PPA Information' form includes the following fields:

- Agreed Rate*
- PPA Signed Date*
- Signed PPA (PDF < 2MB) No file chosen
- Remarks not exceeding 1000 characters

At the bottom of the form, there are two buttons: 'Submit PPA' and 'Reject Application'.







Work Completion Step

Application Info **Feasibility** **PPA** **Work Completion** **Commissioning**

Application No. 1000017513 Feasible Solar capacity in kWp : 160.0

The work of installation of SRTPV system is completed and I would like to submit the following information for your kind needful.

Solar PV Module

Sl No.	Make of the PV Module	Type of the PV Module	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input style="width: 20px; height: 20px;" type="button" value="+"/>	<input style="width: 20px; height: 20px;" type="button" value="-"/>

Total PV Panel capacity (in kWp) 0

Inverter

Sl No.	Make of the Inverter	Type of the Inverter	Capacity of the Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input style="width: 20px; height: 20px;" type="button" value="+"/>	<input style="width: 20px; height: 20px;" type="button" value="-"/>

Total Inverter capacity (in kVA) 0

Meter Details

Sl. No.	Particulars	Main Meter	Check Meter
1	Make	<input type="text"/>	<input type="text"/>
2	Type	<input type="text"/>	<input type="text"/>
3	Sl No.	<input type="text"/>	<input type="text"/>
4	Phase	<input type="text"/>	<input type="text"/>
5	CT Ratio	<input type="text"/>	<input type="text"/>
6	PT Ratio	<input type="text"/>	<input type="text"/>
7	Date of Test by MT Division	<input type="text"/>	<input type="text"/>
8	Meter Testing Report (PDF less than 2 MB)	<input type="button" value="Choose File"/> No file chosen	<input type="button" value="Choose File"/> No file chosen

Declaration

I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arrestor are installed as per Technical Specification

System Installer Details

System Installer Firm Name

System Installer Firm GST Number

Work Declaration form (Download here) No file chosen

Meter Details

Sl. No.	Particulars	Main Meter	Check Meter
1	Make	<input type="text"/>	<input type="text"/>
2	Type	<input type="text"/>	<input type="text"/>
3	Sl No.	<input type="text"/>	<input type="text"/>
4	Phase	<input type="text"/>	<input type="text"/>
5	CT Ratio	<input type="text"/>	<input type="text"/>
6	PT Ratio	<input type="text"/>	<input type="text"/>
7	Date of Test by MT Division	<input type="text"/>	<input type="text"/>
8	Meter Testing Report (PDF less than 2 MB)	<input type="button" value="Choose File"/> No file chosen	<input type="button" value="Choose File"/> No file chosen

Declaration

I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arrestor are installed as per Technical Specification

System Installer Details

System Installer Firm Name

System Installer Firm GST Number

Work Declaration form (Download here) No file chosen

DSPV ONLINE SERVICES

[APPLY ONLINE](#) [APPLY ONLINE \(SOORA GRUHA YOJANE\)](#) [APPLY ONLINE \(GOVT. BUILDINGS\)](#) [VIEW STATUS](#) [OFFICERS' LOGIN](#)

Application Info
 Feasibility
 PPA
 Work Completion
 Commissioning

Application No. 1000017513 Feasible Solar capacity in kWp : 160.0

The work of installation of SRTPV system is completed and I would like to submit the following information for your kind needful.

Solar PV Module

Sl No.	Make of the PV Module	Type of the PV Module	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Mono	0.500	320	Test01,Test02,Test03,Tes	160	+	-
Total PV Panel capacity (in kWp)						160.000		

Inverter

Sl No.	Make of the Inverter	Type of the Inverter	Capacity of the Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Hybrid	160	1	Test	160	+	-
Total Inverter capacity (in kVA)						160		

Meter Details

Sl. No.	Particulars	Main Meter	Check Meter
1	Make	M/s Genus Power Infrastructures Lir	M/s Genus Power Infrastructures Lir
2	Type	ELECTRO STATIC METER	ELECTRO STATIC METER
3	Sl No.	Test	Test
4	Phase	Three Phase	Three Phase
5	CT Ratio	0	0
6	PT Ratio	0	0
7	Date of Test by MT Division	08/08/2025	08/08/2025
8	Meter Testing Report (PDF less than 2 MB)	Choose File Application...145154.pdf	Choose File Application...145154.pdf

Declaration

I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arressor are installed as per Technical Specification

System Installer Details

System Installer Firm Name:

System Installer Firm GST Number:

Work Declaration form (Download here):

Submit
Clear

DSPV ONLINE SERVICES

[APPLY ONLINE](#) [APPLY ONLINE \(SOORA GRUHA YOJANE\)](#) [APPLY ONLINE \(GOVT. BUILDINGS\)](#) [VIEW STATUS](#) [OFFICERS' LOGIN](#)

Meter Details

Sl. No.	Particulars	Main Meter	Check Meter
1	Make	M/s Genus Power Infrastructures Lir	M/s Genus Power Infrastructures Lir
2	Type	ELECTRO STATIC METER	ELECTRO STATIC METER
3	Sl No.	Test	Test
4	Phase	Three Phase	Three Phase
5	CT Ratio	0	0
6	PT Ratio	0	0
7	Date of Test by MT Division	08/08/2025	08/08/2025
8	Meter Testing Report (PDF less than 2 MB)	Choose File Application...145154.pdf	Choose File Application...145154.pdf

Declaration

I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arressor are installed as per Technical Specification

System Installer Details

System Installer Firm Name:

System Installer Firm GST Number:

Work Declaration form (Download here):

Submit
Clear

srtpv.bescom.org says
Please confirm the details entered. Do you wish to continue?

OK Cancel

Meter Details

Sl. No	Particulars	Main Meter	Check Meter
1	Make	M/s Genus Power Infrastructures Lir	M/s Genus Power Infrastructures Lir
2	Type	ELECTRO STATIC METER	ELECTRO STATIC METER
3	SI No.	Test	Test
4	Phase	Three Phase	Three Phase
5	CT Ratio	0	0
6	PT Ratio	0	0
7	Date of Test by MT Division	08/08/2025	08/08/2025
8	Meter Testing Report (PDF less than 2 MB)	Choose File Application...145154.pdf	Choose File Application...145154.pdf

Declaration

I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arressor are installed as per Technical Specification

System Installer Details

System Installer Firm Name: Test

System Installer Firm GST Number: Test

Work Declaration form (Download here): Choose File | Application_1000017513_11082025_145154.pdf

Submit Clear

APPLY ONLINE APPLY ONLINE (SOORA GRUHA YOJANA) APPLY ONLINE (GOVT. BUILDINGS) VIEW STATUS OFFICERS' LOGIN

Meter Details

Sl. No	Particulars	Main Meter	Check Meter
1	Make	M/s Genus Power Infrastructures Lir	M/s Genus Power Infrastructures Lir
2	Type	ELECTRO STATIC METER	ELECTRO STATIC METER
3	SI No.	Test	Test
4	Phase	Three Phase	Three Phase
5	CT Ratio	0	0
6	PT Ratio	0	0
7	Date of Test by MT Division	08/08/2025	08/08/2025
8	Meter Testing Report (PDF less than 2 M	Choose File Application...145154.pdf	Choose File Application...145154.pdf

Declaration

I declare that other equipment such as DC/AC Cabels, AJB/DC distribution box, Earthing, DC/AC Surge arressor are installed as per Technical Specification

System Installer Details

System Installer Firm Name: Test

System Installer Firm GST Number: Test

Work Declaration form (Download here): Choose File | Application_1000017513_11082025_145154.pdf

Submit Clear

Verify OTP and Submit

OTP has been sent to registered consumer mobile number

Enter OTP

Verify & Submit Resend OTP

The screenshot shows a web application interface for BESCOM. A dark notification box at the top center displays the message: "srtpv.bescom.org says Work execution details successfully submitted." with an "OK" button. Below this, a "Verify OTP and Submit" dialog box is open, containing the text: "OTP has been sent to registered consumer mobile number" and a text input field with the value "1254". The dialog has "Verify & Submit" and "Resend OTP" buttons. In the background, the "Meter Details" form is visible, featuring a table with columns for "Sl. No", "Particulars", "Main Meter", and "Check Meter". The table contains 8 rows of data. Below the table are sections for "Declaration" (with a checked checkbox) and "System Installer Details" (with fields for firm name, GST number, and a file upload button).

Sl. No	Particulars	Main Meter	Check Meter
1	Make	M/s Genus Power Infrastructures Lri	M/s Genus Power Infrastructures Lri
2	Type	ELECTRO STATIC METER	ELECTRO STATIC METER
3	Sl No.		Test
4	Phase		Three Phase
5	CT Ratio		0
6	PT Ratio		0
7	Date of Test by MT Division		08/08/2025
8	Meter Testing Report (PDF less than 2 M)		Choose File Application...145154.pdf

The screenshot shows the "DSPV ONLINE SERVICES" page in a browser. The URL is "srtpv.bescom.org/SRTPV_TEST/application_tracker_work_execution.jsp?applicationno=1000017513". The page has a navigation bar with "APPLY ONLINE" and "OFFICERS' LOGIN" links. A central panel displays the application status: "Application No. 1000017513" and "Feasible Solar capacity in kWp : 160.0". Below this, there are two green buttons: "Download Work Execution Details Submitted" and "Download System Installer Declaration Letter". The footer contains the text "@ 2020 - Design By BESCOM" and "080 2234 0816 solar_helpdesk@bescom.co.in". The browser's taskbar at the bottom shows the system time as 3:28 PM on 8/11/2025.

Application_1000017513_WorkExecution_11_08_2025_15_28_4... 1 / 2 63%

Work Execution details of of SRTPV Application No. 1000017513

Solar PV Module

Sl No	Make	Type	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity
1	Test	Mono	0.5	320	Test01,Test02,Test03,Test03	160.0

Inverter

Sl No	Make	Type	Capacity of Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity
1	Test	Hybrid	160.0	1	Test	160.0

Bidirectional Main Meter

Make	M/s Genus Power Infrastructures Limited
Type	ELECTRO STATIC METER
Serial No	Test
Phase	Three Phase
CT Ratio	0.0
PT Ratio	0.0
Date of Test by MT division	08 Aug 2025

Bidirectional Check Meter

Make	M/s Genus Power Infrastructures Limited
Type	ELECTRO STATIC METER
Serial No	Test
Phase	Three Phase
CT Ratio	0.0
PT Ratio	0.0
Date of Test by MT division	08 Aug 2025
System Installer Firm Name	Test
System Installer Firm License Number	Test

Certified that the above said SRPTV system was installed by me and the equipment's used comply the Technical and Safety standards issued by BESCOM.

Report submitted on : 11 Aug 2025 03:28:19 PM

BESCOM | SRTPV Online Application

srtpv.bescom.org/SRTPV_TEST/application_tracker_application_info.jsp?applicationno=1000017513

INCognito

APPLY ONLINE APPLY ONLINE (SOURA GRUHA YOJANE) APPLY ONLINE (GOVT. BUILDINGS) VIEW STATUS OFFICERS LOGIN



Status History



Status	Changed by	Date	Next Action	Pending with	Remarks
Work completion intimated. Pending commission	Applicant	11 Aug 2025 03:28:19 PM	MT inspection completed. Pending synchronization	S20 Subdivision	
PPA Approved and Work Approval Intimated.	S20 Subdivision	11 Aug 2025 03:21:03 PM	Work completion intimated. Pending commission	Applicant	
PPA Submitted.	S20 Subdivision	11 Aug 2025 03:21:02 PM	PPA Approved and Work Approval Intimated.	S20 Subdivision	PPA Submitted
Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	11 Aug 2025 03:17:30 PM	PPA Submitted.	Applicant	SRTPV is Feasible.
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 02:57:52 PM	Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 02:51:54 PM	Payment Successful. Pending feasibility	Applicant	

For development purposes only

ENG 3:29 PM US 8/11/2025

MT Inspection Step





Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
MT Inspection completed. Pending synchronization	BMAZ-South	11 Aug 2025 03:35:52 PM	Synchronized	S20 Subdivision	
Work completion intimated. Pending commission	Applicant	11 Aug 2025 03:28:19 PM	MT Inspection completed. Pending synchronization	S20 Subdivision	
PPA Approved and Work Approval Intimated.	S20 Subdivision	11 Aug 2025 03:21:03 PM	Work completion intimated. Pending commission	Applicant	
PPA Submitted.	S20 Subdivision	11 Aug 2025 03:21:02 PM	PPA Approved and Work Approval Intimated.	S20 Subdivision	PPA Submitted
Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	11 Aug 2025 03:17:30 PM	PPA Submitted.	Applicant	SRTPV is Feasible.
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 02:57:52 PM	Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 02:51:54 PM	Payment Successful. Pending feasibility	Applicant	

Commission Step

Commissioning

Application No. 1000017513 Feasible Solar capacity in kWp : 160.0

Notes:

- The Bi-directional meter records solar generation and existing meter records installation consumption in case of Gross metering.
- The Bi-directional meter records export of solar energy to grid and Import of energy by the installation. Existing meter records the total solar energy generated.

Notes: The following verification has to be done scrupulously during field inspection:

- Verify the sl no. nos of modules and capacity of each panel with agreed capacity in the Power purchase agreement. In case of any variation SPPA shall be made.
- Verify the details of grid tied inverters and meters.
- In case any changes / modifications or observations to be made/ attended by the consumer the same shall be returned back to consumer to attend the same (by clicking the return button along with reasons).
- The SPPA shall be made in case of delay in commissioning.
- The SRTPV plant shall be synchronized with 5 days from the date of submission of work completion or after attending the observations whichever is later.
- The other norms of the SRTPV tariff order / Regulation issued from time to time is applicable.

Work Declaration Details [Download](#)

Meter Information

	Bi-Direction Meter (Main)*	Bi-Direction Meter (Check)*	Existing Meter*
Meter make:	M/s Genus Power Infra	M/s Genus Power Infra	M/s Genus Power Infra
Meter phase:	Three Phase	Three Phase	Three Phase
Meter Type:	ELECTRO STATIC MET	ELECTRO STATIC METE	ELECTRO STATIC ME
Serial number:	Test	Test	Test
Meter constant:	0.0	0.0	0.0
Initial reading (Tri vector parameters) Import:	0.0	0.0	0.0

Meter Information

Bi-Direction Meter (Main)*		Bi-Direction Meter (Check)*		Existing Meter*	
Meter make:	M/s Genus Power Infra	M/s Genus Power Infra	M/s Genus Power Infra	M/s Genus Power Infra	M/s Genus Power Infra
Meter phase:	Three Phase	Three Phase	Three Phase	Three Phase	Three Phase
Meter Type:	ELECTRO STATIC MET	ELECTRO STATIC METE	ELECTRO STATIC METE	ELECTRO STATIC ME	ELECTRO STATIC ME
Serial number:	Test	Test	Test	Test	Test
Meter constant:	0.0	0.0	0.0	0.0	0.0
Initial reading (Tri vector parameters) Import:	0.0	0.0	0.0	0.0	0.0
Initial reading (Tri vector parameters) Export:	0.0	0.0	0.0	0.0	0.0

Solar PV Module

Sl No.	Make of the PV Module	Type of the PV Module	Capacity of each module in kWp	No. of Modules	Sl. No of Modules (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Mono	0.5	320	Test01,Test02,Ti	160.0	+	-

Total PV Panel capacity (in kWp) 160.0

Grid Tied Inverter

Sl No.	Make of the Inverter	Type of the Inverter	Input voltage (volts)	Output voltage (volts)	Capacity of the Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity	Add	Delete
1	Test	Hybrid	220	220	160.0	1	Test	160.0	+	-

Total Inverter capacity (in kVA) 160.0

Inspection Details

Inspection Details

Pincode: 560023

District of the installation: 525,BENGALURU URBAN

Latitude of the installation: 12.983492708088045

Longitude of the installation: 77.57777144013671

Locate Latitude & Longitude on Google Map OR Use my current location

Whether Anti-islanding feature is in working condition? * Yes No

Is DC earthing verified? * Yes No

Is AC earthing verified? * Yes No

Is LA earthing verified? * Yes No

Is AC & DC DB available? * Yes No

Is Manual Switch on solar side available? * Yes No

Is Relay operated automatic switch at net-meter side available? * Yes No



Date of Inspection: 10/08/2025

Photo of the plant along with the Prosumer (JPEG file < 2 MB): IMG-2...001.jpg

Date of synchronizing with BESCOM grid: 11/08/2025

Synchronization Voltage Level: 220

Commission Done:



Application_1000017513_Commissioning_11_08_2025_15_39... 1 / 2 53%

BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED
Wholly owned Govt. of Karnataka Undertaking

Commissioning details of srtpv Application No. 1000017513

Meters

	Bi-directional Main Meter	Bi-directional Check Meter	Existing Meter
Make	M/s Genus Power Infrastructures Limited	M/s Genus Power Infrastructures Limited	M/s Genus Power Infrastructures Limited
Type	ELECTRO STATIC METER	ELECTRO STATIC METER	ELECTRO STATIC METER
Phase	Three Phase	Three Phase	Three Phase
Meter constant	0.0	0.0	0.0
Initial Reading (Import)	0.0	0.0	0.0
Initial Reading (Export)	0.0	0.0	0.0

Solar PV Panels

Sl No	Make	Type	Capacity of each module (Wp)	No. of modules	Sl. No of modules (Comma separated)	Total capacity of this make, type & capacity
1	Test	Monc	0.5	320	Test01,Test02,Test03,Test03	160.0

Inverter

Sl No	Make	Type	Input Voltage	Output Voltage	Capacity of Inverter (kVA)	No. of Inverters	Sl. No of Inverters (Comma separated)	Total capacity of this make, type & capacity
1	Test	Hybrid	220.0	220.0	160.0	1	Test	160.0

Inverter

Is Anti-Islanding feature Available ?	Yes
Is DC earthing verified ?	Yes
Is AC earthing verified ?	Yes
Is LA earthing verified ?	Yes
Is AC & DC DB available ?	Yes
Is Manual Switch on solar side available ?	Yes
Is Relay operated automatic switch at net-meter side available ?	Yes
Date of inspection	10 Aug 2025
Date of Synchronization to BESCOM grid	11 Aug 2025

Synchronization Voltage Level: 220

Report submitted on: 11 Aug 2025 05:39:28 PM

Application_Synchronization_Certificate1000017513_11082025... 1 / 1 75%

BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED
Wholly owned Govt. of Karnataka Undertaking

Ref: Office of the Assistant Executive Engineer(Ele),
S20 subdivision, BESCOM, Agara, Bengaluru
Date: 11.08.2025

To,
M/S TRIDENT AUTOMOBILES PVT LT
CAR SHOWROOMNAGANATHAPURA

Madam/Sir,

Sub: Certificate of synchronization of your SRTPV system

Ref: Application Reg No. 1000017513 dated 11.08.2025

Synchronization test of Solar Rooftop PV system of 160.0 kWp, installed on the roof of your installation bearing RR No.: SBHT274 has been conducted and your SRTPV system successfully synchronized with the BESCOM grid at 220 voltage level on 11.08.2025

Yours Faithfully
sd/-
Assistant Executive Engineer(Ele)
S20 Subdivision
, BESCOM.

Status History

Status	Changed by	Date	Next Action	Pending with	Remarks
Synchronized	S20 Subdivision	11 Aug 2025 03:39:29 PM	null		Commission Done
MT Inspection completed. Pending synchronization	BMAZ-South	11 Aug 2025 03:35:52 PM	Synchronized	S20 Subdivision	
Work completion intimated. Pending commission	Applicant	11 Aug 2025 03:28:19 PM	MT Inspection completed. Pending synchronization	S20 Subdivision	
PPA Approved and Work Approval Intimated.	S20 Subdivision	11 Aug 2025 03:21:03 PM	Work completion intimated. Pending commission	Applicant	
PPA Submitted.	S20 Subdivision	11 Aug 2025 03:21:02 PM	PPA Approved and Work Approval Intimated.	S20 Subdivision	PPA Submitted
Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	11 Aug 2025 03:17:30 PM	PPA Submitted.	Applicant	SRTPV is Feasible.
Payment Successful. Pending feasibility	Applicant	11 Aug 2025 02:57:52 PM	Feasibility Completed. Intimated for submitting PPA	S20 Subdivision	
Registered. Pending for payment	Applicant	11 Aug 2025 02:51:54 PM	Payment Successful. Pending feasibility	Applicant	